



NOW PLAYING

Design and behaviour guide

The music player, the hub, the Windows companion, the Android app and the Discord bot: one Aqua system, its rules, every screen, and how to keep it true.

PROFILE

snow-leopard-itunes-9

SOURCE FINGERPRINT

2e5edf99053c1f3e

COVERAGE

68 surfaces · 11 journeys · 72 rules

INTERACTIVE VERSION

<docs/design/styleguide.html>

Contents

PRINCIPLES

The four rules	
Brand and voice	

FOUNDATIONS

Colour	
Aqua highlights	
Type	

ELEMENTS

The page (player)	
The window (hub, companion)	
Controls	
Overlays	

BEHAVIOUR

Interaction rules	
Accessibility	
Every screen	

MOCKUPS

Every product, every size	
---------------------------	--

UPKEEP

Sources and commands	
Changing it	

Two skins	
-----------	--

Space	
Shape and material	
Motion	

States	
Results and grid	
Icons	
By product	

Journeys	
The Discord bot	
Platforms	

Coverage and decisions	
------------------------	--

Now Playing styleguide

snow-leopard-itunes-9 · 118 colours · two skins · 68 surfaces · source 2e5edf99053c1f3e

A reconstruction of Apple's 2009–2010 interface, built as one design system and shared by every part of Now Playing: the music player (a page, also inside the Android app), the hub's admin GUI and the Windows companion (both windows), and the words the Discord bot uses. Every value here is read from `tokens.json` as this page is built, every control on it is the real component wearing the real stylesheet, and every rule, screen and journey is read from `design/` — so the page cannot describe one thing and show another.

The rules that outrank the visuals

A styleguide that opens with colour teaches the wrong lesson. These four decide whether a control is drawn at all, and each has overruled the aesthetics here at least once.

UX-PRIN-001

A control that cannot act is not drawn

No button that looks live and does nothing, no toggle whose state is decoration. If an action is impossible in this context the control is omitted or replaced by an explained state. The equalizer window ships without traffic lights: three circles that close nothing would be decoration.

UX-PRIN-002

An unavailable capability says so where the choice is made

Not in a tooltip, not in a log, not by disappearing. The control stays visible and, when chosen, reports the reason instead of acting. The Shared segment of the mode switch stays visible with no hub paired and reports why when pressed.

UX-PRIN-003

Say what the code does, not what the feature is called

Labels describe the implemented behaviour. When a label and the DSP (or the network, or the provider) disagree, the label changes. Solfeggio presets are described as filters with no claimed physical effect; retuning states that the fallback changes tempo.

UX-PRIN-004

A disabled control is still legible about why

Greyed, not gone. The reason is part of the accessible name, not only a tooltip. “500 Hz band, not used by 528 Hz (MI)”.

Brand and voice

Now Playing is a self-hosted music suite: a player that works on the files you already have, a hub you run yourself, and a companion that brings a Windows library to it. Its look is a careful reconstruction of Apple's 2009–2010 interface — the Snow Leopard window, the iTunes 9 list, the iPod's Now Playing screen — chosen for its density and its honesty about state. The reference is `docs/design/APPLE_AQUA_2009_2010_UI_DESIGN_SPEC.md`.



Now Playing Player

music-player/public/icon.svg


Also the Android launcher (brand colour #3b74c8) and the maskable PWA icon.



Now Playing Companion for Windows

windows-companion/resources/icon.svg

The same tile with a folder behind the note: the one app that reaches the filesystem.



The note

packages/aqua-ui/src/icons/glyphs.tsx

Both icons draw this exact path; a unit test fails if they drift apart again.

USING THE MARK

- The tile is a rounded square (radius 112 on a 512 grid), a three-stop blue gradient and a soft gloss over the top half. Keep all three; the gloss is the period detail.
- Never recolour the note or redraw it by hand. Use the SVG or the `note` glyph.
- The blue tile is the product's mark. Inside the interface blue is never decoration — it means selected, active or default (see Colour).
- ● **PROPOSED** Clear space and minimum size have not been specified. Until they are, keep a quarter of the tile's width clear around it and do not use it below 16px; the tray icon is its own simplified drawing.

VOICE

Plain, specific and a little dry. The product explains what it is doing and what it cannot do, in the place you are looking. It does not apologise, cheer or use exclamation marks, and it never claims more than the code does (UX-PRIN-003).

VOICE-001

Empty states say what to do next ● OBSERVED

Title names the situation in a few plain words ("Nothing queued"); text gives the next action or the reason. No apologies, no exclamation marks. "Nothing queued — Play something from your library and it will appear here."

VOICE-002

Errors explain the problem and the way out ● ADOPTED

Name what failed in the person's terms and what fixes it ("Add a bot token first (Admin → Discord → Token)"). Never show a stack trace or an internal identifier; a 500 carries a correlation id instead.

VOICE-003

One product name, set in one place ● ADOPTED

"Now Playing" and the product names come from BRANDING in TypeScript. Native resources that cannot import it (Android strings.xml, the SVG icons' aria-labels, the Electron builder config) repeat it and must be changed together.

WORDS WE USE

SAY	MEANING	NOT
Now Playing	The suite. Its parts are “the player”, “the hub” and “the companion”.	Other product names invented per screen
Solo / Shared listening	The two modes on the status bar.	Party mode, sync mode
Group	People listening to one shared queue on a hub.	Room, session
Pair	Connecting a device to a hub, confirmed by a fingerprint.	Log in, register a device
Shared link	A public link to a track or playlist the hub serves.	Share URL, public page
Fetch	Running yt-dlp or spotDL on this machine.	Rip, grab
Hub library	Files that live on the hub’s data volume.	Cloud, server music

● OBSERVED The vocabulary above is how the code and the docs already talk; it has not been reviewed as a glossary.

REAL COPY

Nothing queued

Play something from your library and it will appear here.

Player · Queue

No folders yet

Add the folder your music is in. The companion indexes it in place; your files are never copied or moved.

Companion · Folders

Nothing to show yet

Play some music and this fills in. Everything here is worked out on this device from a log that never leaves it.

Player · Listening history

Search your music

Searches the music on this device. Pair a hub in Settings to search connected services too.

Player · Search

Two skins, one system

The same profile in two arrangements. A window frame drawn inside a browser viewport is a picture of a window rather than a window, and a 196 px source list is simply unavailable on a phone — so the player is a page while the desktop products stay windows. Controls are shared verbatim between them.

Window skin

--aqua-* · aqua.css, aqua-window.css, aqua-media.css · Lucida Grande · hub admin GUI, Windows companion

Page skin




--np-*, --lib-* · now-playing.css · Helvetica, the iPod's face · music player PWA

Colour




Chosen by role, never by picking a hex. Blue means *selected*, *active*, or *the default action* — it is not a brand colour and it is never decoration. Two palettes follow, straight from the token file: the window skin's, then the page skin's.

WINDOW SKIN — 91 TOKENS


WINDOW AND CONTENT

 desktop #6D737A	 windowOutline #747474	 windowBody #ECECEC	 content #FFFFFF
 contentMuted #F7F7F7	 rowStripe #F1F6FB	 rowDivider #D8DEE5	


CHROME

 chromeTop #F6F6F6	 chromeUpper #E5E5E5	 chromeLower #C4C4C4	 chromeBottom #AFAFAF
 chromeSeparator #858585	 chromeHighlight #FFFFFF		



SOURCE LIST

 sidebarTop #DCE8F4	 sidebarBottom #BCEEE0	 sidebarDivider #93A3B2	 sidebarGroupText #536473
--	---	---	--



SELECTION AND FOCUS

 selectionTop #69B5F3	 selectionMid #378DDA	 selectionBottom #1764B2	 selectionBorder #0F4E8B
 selectionText #FFFFFF	 focus #3F9FE8		

AQUA GEL

 aquaSpecular #EAFBFF	 aquaTop #A9E5FF	 aquaMid #38B6F7	 aquaLower #0D83D6
 aquaBottom #075FA6	 aquaRim #07558F		



GRAPHITE

 graphiteTop #E5E7E9	 graphiteMid #AEB4B9	 graphiteBottom #737A80
---	---	---


TEXT

 text #161616	 textSecondary #565B60	 textDisabled #96999C
--	---	---


LCD

 lcdTop #E1EAE8	 lcdBottom #AEBCC0	 lcdText #172326
--	---	--



















STATUS


 danger #D64A44	 warning #D9A431	 success #4E9D47
--	---	--

TRAFFIC LIGHTS

 trafficClose #E9635B	 trafficMinimize #E3B64B	 trafficZoom #58A953
--	---	--





OTHER

 headerTop #F8F8F8	 headerBottom #DADADA	 headerRule #ADADAD	 headerText #3A3D41
 warningBg #FBF3DC	 warningEdge #D8B75E	 ctlInk #151515	 ctlFace1 #FDFDFD
 ctlFace2 #F4F4F4	 ctlFace3 #E6E6E6	 ctlFace4 #DCDCDC	 ctlFaceHover1 #FFF
 ctlFaceHover2 #F8F8F8	 ctlFaceHover3 #ECECEC	 ctlFaceHover4 #E3E3E3	 ctlFaceActive1 #C9C9C9
 ctlFaceActive2 #D6D6D6	 ctlFaceActive3 #DEDEDE	 ctlFaceDisabled1 #FBFBFB	 ctlFaceDisabled2 #F1F1F1
 ctlBorder #A3A3A3	 ctlBorderBottom #8D8D8D	 ctlBorderDisabled #C9C9C9	 ctlFocusRing #0D61A7
 ctlDefaultInk #06203A	 ctlDefault1 #CFEAFB	 ctlDefault2 #A3D4FB	 ctlDefault3 #74B9F5
 ctlDefault4 #5AA8EF	 ctlDefaultBorder #4684C8	 ctlDefaultBorderBottom #356DB0	 ctlBoxInk #1A2733
 ctlBox1 #FDFDFD	 ctlBox2 #F0F0F0	 ctlBox3 #E4E4E4	 ctlBoxBorder #A0A0A0
 ctlBoxOn1 #7DB4E6	 ctlBoxOn2 #4F92D6	 ctlBoxOn3 #3F81C6	 ctlBoxOnBorder #3D76AD


			
ctlFieldBg #FFF	ctlFieldBorder #9A9A9A	ctlFieldBorderTop #7D7D7D	ctlFieldFocusBorder #1768A7
			
ctlFieldInvalidBorder #B8433D	ctlPlaceholder #8B9095	dangerInk #7A1712	

PAGE SKIN — 25 TOKENS


STATUS BAR

			
barTop #F5F6F7	barUpper #E8EAEA	barLower #DCE2DE	barBottom #D9DFE1
			
barEdge RGB(31 41 45 / 22%)			




FIELD

	
fieldTop #F2F2F2	fieldBottom #FFFFFF




MODE SWITCH

			
modeFaceTop #FDFDFD	modeFaceBottom #DCDEE0	modeOnTop #767C85	modeOnBottom #A9B0B8

SCRUBBER

			
railTop #E9ECEE	railBottom #FFFFFF	railFillTop #8FB9E4	railFillMid #2B9BEC
			
railFillBottom #A5E9FD			

LIST

 listHeaderTop #F8F8F8	 listHeaderBottom #DADADA	 listSortTop #E8EEF7	 listSortBottom #CFDBEB
 listStripe #F2F5F9	 listPlaying #DDE9F8	 listSelectTop #5B8DD9	 listSelectBottom #3A6CC4

MARKS

 live #CC1027	 star #F0A422
--	--

DARK

The page skin has a full dark palette and it is opt-out: every dark rule is guarded `@media (prefers-color-scheme: dark) { :root:not([data-np-theme='light']) { ... } }`, so the system preference wins unless a page pins itself light. Redefine *only* tokens inside that block. The window skin has no dark palette, because Snow Leopard had none.

The page skin's colours that change in the dark scheme, read from the shipped stylesheet when this page was built (88 properties). Light on the left, dark on the right.

--ctx-bg rgb(247 247 250 / 88%) → rgb(40 42 48 / 90%)	 	--lib-head-hot-bot #cfcfcf → #303338	 
--ctx-ink #1b1c1f → #eef0f3	 	--lib-head-hot-top #efefef → #45484f	 
--ctx-sep rgb(0 0 0 / 12%) → rgb(255 255 255 / 12%)	 	--lib-head-ink #3a3d41 → #c6cbd3	 
--lib-accent #2b6fd6 → #6aa3f2	 	--lib-head-rule #adadad → #0f1114	 
--lib-alt #f2f5f9 → #1b1f26	 	--lib-head-sep #ccc → #17191d	 
--lib-bg #fff → #16181c	 	--lib-head-top #f8f8f8 → #3a3d44	 
--lib-border #ababab → #08090b	 	--lib-icon #8a8f98 → #8d939c	 
--lib-head-bot #dadada → #26292e	 	--lib-ink #000 → #f2f3f5	 
--lib-head-emboss rgb(255 255 255 / 80%) → rgb(0 0 0 / 55%)	 	--lib-np #dde9f8 → #22354f	 


--lib-soft #222326 → #d4d8df	 	--np-bar-top #f5f6f7 → #34373d	 
--lib-sort-bot #cfdbeb → #233043	 	--np-field-bottom #fff → #24272d	 
--lib-sort-hot-bot #c2d2e6 → #2b3b52	 	--np-field-hint #ababab → #7c8087	 
--lib-sort-hot-top #dde7f4 → #36485f	 	--np-field-icon #8e8e91 → #85898f	 
--lib-sort-top #e8eef7 → #2c3a4e	 	--np-field-lip rgb(255 255 255 / 70%) → rgb(255 255 255 / 8%)	 
--lib-star #f0a422 → #f4b241	 	--np-field-mid #fbfbfb → #1b1e23	 
--np-accent #2b6fd6 → #6aa3f2	 	--np-field-ring rgb(0 0 0 / 20%) → rgb(0 0 0 / 70%)	 
--np-avatar-face #f3f3f3 → #2b2e34	 	--np-field-shadow rgb(0 0 0 / 32%) → rgb(0 0 0 / 75%)	 
--np-avatar-lip rgb(255 255 255 / 70%) → rgb(255 255 255 / 10%)	 	--np-field-top #f2f2f2 → #141619	 
--np-avatar-ring rgb(0 0 0 / 26%) → rgb(0 0 0 / 55%)	 	--np-ink #1b1c1f → #f1f2f4	 
--np-bar-1 #eef0f1 → #2f3238	 	--np-key-ink #1b1c1f → #ccd1d8	 
--np-bar-2 #e8eaea → #2a2d33	 	--np-key-muted #8b9099 → #7f858e	 
--np-bar-3 #e2e6e5 → #25282e	 	--np-key-on #2f6ec0 → #5fa0ea	 
--np-bar-4 #dfe4e1 → #212429	 	--np-list-alt #f2f5f9 → #1b1f26	 
--np-bar-5 #dce2de → #1e2126	 	--np-list-badge #dfe3e9 → #2f333b	 
--np-bar-bottom #d9dfe1 → #1a1d22	 	--np-list-badge-ink #3b3f47 → #d6dae1	 
--np-bar-edge rgb(31 41 45 / 22%) → rgb(0 0 0 / 60%)	 	--np-list-border #ababab → #08090b	 
--np-bar-emboss rgb(255 255 255 / 55%) → transparent	 	--np-list-icon #8a8f98 → #8d939c	 

--np-live	 	--np-vol-face	 
#cc1027 → #ff4d62		#fff → #1b1e23	
--np-live-halo	 	--srch-art-bot	 
rgb(204 16 39 / 32%) → rgb(255 77 98 / 36%)		#e3e3e3 → #24262b	
--np-meta	 	--srch-art-ink	 
#575757 → #9ba0a8		#a9a9a9 → #8d939c	
--np-page	 	--srch-art-ring	 
#fff → #0e0f12		rgb(0 0 0 / 14%) → rgb(255 255 255 / 10%)	
--np-rail-line	 	--srch-art-top	 
rgb(0 0 0 / 16%) → rgb(0 0 0 / 72%)		#fbfbfb → #33363d	
--np-seg-border	 	--srch-bg	 
rgb(0 0 0 / 36%) → rgb(0 0 0 / 70%)		#f9f9f9 → #26282e	
--np-seg-divider	 	--srch-border	 
rgb(0 0 0 / 30%) → rgb(0 0 0 / 55%)		rgb(0 0 0 / 25%) → rgb(0 0 0 / 65%)	
--np-seg-face-bottom	 	--srch-chev	 
#dcdee0 → #292c31		#8f8f8f → #9aa0a9	
--np-seg-face-mid	 	--srch-dot	 
#f0f1f2 → #33363c		#c9c9c9 → #4a4e56	
--np-seg-face-top	 	--srch-dot-on	 
#fdfdfd → #3a3d44		#7c7c7c → #b8bdc5	
--np-seg-ink	 	--srch-head-bot	 
#43464b → #c3c7cf		#eee → #25272d	
--np-seg-lip	 	--srch-head-top	 
rgb(255 255 255 / 65%) → rgb(255 255 255 / 8%)		#f6f6f6 → #2e3138	
--np-seg-on-bottom	 	--srch-hot	 
#a9b0b8 → #23262c		#ececec → #32353c	
--np-seg-on-mid	 	--srch-ink	 
#939aa3 → #1c1f24		#2c2c2c → #eef0f3	
--np-seg-on-top	 	--srch-lip	 
#767c85 → #14161a		rgb(255 255 255 / 60%) → rgb(255 255 255 / 7%)	
--np-vol-a	 	--srch-rule	 
#9aa1a9 → #6e747c		#dedede → rgb(0 0 0 / 50%)	
--np-vol-b	 	--srch-soft	 
#b7bdc4 → #878e96		#9b9b9b → #8d939c	

Aqua highlights — where the blue is allowed to shine


Snow Leopard had flattened most of Aqua's gel by 2009, but not all of it: selection, the default action, the scroller and a few controls kept the glass. Those are exactly the places this system keeps it, and this is each one, live.

THE DEFAULT ACTION



The one button on a form that carries the Aqua blue: a pale cyan cap over a saturated body, a specular hairline at the top, a dark rim, and a slow pulse. The shape stays the Snow Leopard rounded rect — no pill, no glass lozenge, no gloss step across the middle.

SELECTION




The source list's selected row is the blue gel gradient with white text, as in every OS X sidebar; the music list's selected row is the same blue at the page skin's tint; the sorted column is the palest tint of the three.

CONTROLS THAT KEEP THE GEL




The checked box, the pop-up's end cap, the aqua-tinted segmented control and the indeterminate progress bar's barber pole are the last four places a form is blue.

THE OVERLAY SCROLLER



The full five-stop Aqua gel survives at strength in exactly one place: the list's overlay scroller, which fades in while you scroll and out 900 ms after you stop.

THE IPOD RAIL



Not gel, but the other blue on the page: the iPod Classic's progress bar, 12 px, near-square ends, and a fill that brightens downward — sky at the top through a saturated dip at 62% to a cyan glow along the lower lip. No knob: the device had none.

And the focus ring — `--aqua-focus #3F9FE8` with a soft outer glow — is blue everywhere, because the thing that has the keyboard is the one thing on screen that must never be ambiguous.

Type

Two families, one scale. The window skin sets Lucida Grande, as OS X did. The page skin sets **Helvetica** — the face the iPod classic drew its Now Playing screen in, which is what the hero is modelled on — with Arial as its metric-compatible stand-in where Helvetica is absent. Each specimen is at its true size.

PAGE SKIN · HELVETICA

13px	Sundress — A\$AP Rocky	<code>--aqua-font-system</code>
12px	Marlow & the Tidewater — Quiet Arithmetic	<code>--aqua-font-view</code>
11px	Searches this device only until a hub is paired	<code>--aqua-font-small</code>
10px	PREAMP · 32 · 64 · 125 · 250 · 500 · 1K · 2K	<code>--aqua-font-label</code>
9px	Mini controls only	<code>--aqua-font-mini</code>

WINDOW SKIN · LUCIDA GRANDE

13px	Now Playing	<code>--aqua-font-system</code>
12px	Copper Meridian — Orbital Cartographers	<code>--aqua-font-view</code>
11px	1,240 songs, 2.6 hours, 245 MB	<code>--aqua-font-small</code>

10px	LIBRARY · PLAYLISTS · CONNECTED	--aqua-font-label
9px	Mini controls only	--aqua-font-mini

Weights are **400** and **700**. There is no 500 and no 600: the profile predates variable UI fonts, and a half-weight reads as a rendering fault beside a true bold. Numbers that change in place — timers, dB values, tempo, track times — take font-variant-numeric: tabular-nums, so a changing digit does not shift the ones beside it.

Space

One scale, no arbitrary values. Each bar is drawn at its true width.

--aqua-space-micro	2px	
--aqua-space-tight	4px	
--aqua-space-inline	6px	
--aqua-space-control	8px	
--aqua-space-small-group	10px	
--aqua-space-group	12px	
--aqua-space-frame-top	14px	
--aqua-space-strong-group	16px	
--aqua-space-window-edge	20px	
--aqua-space-major	24px	
--aqua-space-bottom-bar-regular	32px	

SIZES

visualControlRegular 22PX	visualControlSmall 19PX	searchRegular 22PX	tableRow 20PX
listRow 18PX	railHeight 12PX	transportKey 48PX	playKey 64PX
barHeight 40PX	sidebarDefault 196PX		

32 px (--aqua-hit) is the floor for a pointer target, and **44 px** on a coarse pointer, which is what both platform guidelines ask for. A 12 px rail and an 18 px row are period-correct and stay that size — they get their hit area from an invisible ::after that expands past the visual. Never shrink a hit target to match a visual.

Shape and material

One light source, above and slightly forward. Raised things are light at the top and dark at the bottom; recessed things are the reverse. Every shadow follows from that, and a rule that contradicts it looks broken even when the colours are right.

RADII




THE PUSH BUTTON



A rounded rect, one quiet vertical gradient, a hairline rim that darkens along the bottom, one pixel of white on top. The default action is the same shape with the Aqua blue on it — see the highlights above.


```
background: linear-gradient(to bottom, #fdfdfd 0%, #f4f4f4 47%, #e6e6e6 53%, #dcdcdc 100%);
border: 1px solid #a3a3a3;
border-bottom-color: #8d8d8d;
border-radius: 4px;
box-shadow:
  inset 0 1px 0 rgb(255 255 255 / 90%), /* the pixel of light on the top edge */
  0 1px 0 rgb(255 255 255 / 55%);      /* the surface beneath catching it */
```

RECESSED FIELDS



Wells run the other way: shadowed at the top inside, with the lower lip catching light. Same source, opposite surface. The window skin's search field and the page skin's search pill are the same idea at two heights (22 px and 26 px).

FADERS



The slider's knob is a small lozenge with a pointed edge, the equalizer's fader is the same control rotated; both ride a recessed groove.

Motion

Confirmation, never decoration: nothing animates that a person did not just cause. Everything eases on `cubic-bezier(0.2, 0.7, 0.2, 1)`. Bars are drawn in proportion.

--aqua-motion-press	70ms	
--aqua-motion-selection	100ms	
--aqua-motion-disclosure	140ms	

--aqua-motion-panel	200ms	
--aqua-motion-default-pulse	1650ms	
--aqua-motion-scroller-fade	300ms	

Reduced motion is a contract, not a courtesy. Under prefers-reduced-motion: reduce the live dot stops pulsing, the marquee does not scroll (the cell keeps its ellipsis), the sheet's travel drops to zero and it fades only, the constellation opens as a table rather than an animated field, and the 3D stage stops its idle drift. Two variables carry most of it — --aqua-anim-state: paused and --aqua-sheet-travel: 0 — so a new animation should read one of them rather than inventing a third.

The page — what the player is made of

The music player's skin: a sticky status bar, a section strip, the hero with the jewel case on its stage, the iPod rail and a transport of eleven keys, and the iTunes 10 list under it. Everything below is live — press play and the case opens; pick a row and the stage follows it.

Now Playing

11:08

Q Search your music

Music Library8

Queue6

Playlists

Listening history

Midnight Set, Side B

Fennel Grove

Long Wave Sessions, Vol. 2

00:23

-02:35

#		Song	Artist	Time	BPM		★	Album
1		Copper Meridian	Orbital Cartographers	5:05	—		★	Copper Meridian
2		Ein außerordentl...	Cassette Bloom	6:21	104		★	Live from Pier 9
3		Harbour Lights	Orbital Cartographers	4:24	—		★	Copper Meridian
4		Lantern Road	Marlow & the Tidewater	3:24	118		★	Quiet Arithmetic
5		Long Wave	Fennel Grove	5:16	122		★	Long Wave Sessions, Vol. 2
6		Midnight Set, Side B	Fennel Grove	2:58	110		★	Long Wave Sessions, Vol. 2
7		Pier 9 (Live)	Cassette Bloom	4:11	—		★	Live from Pier 9
8		Quiet Arithmetic	Marlow & the Tidewater	3:51	96		★	Quiet Arithmetic

The transport is centred on the rail. Play sits on the progress rail's centre line at every width, with previous and next either side of it on the same line, and the keys never run past the rail's ends. The volume line sits beside the keys only when it fits on both sides; otherwise it goes beneath, centred, as it does here. When the keys do not fit on one line, previous, play and next take the first line on their own and the other eight keys share the line below. The row measures itself to decide this, because the room it needs depends on how many keys a product carries (DEC-016).

Now Playing styleguide · source 2e5edf99053c1f3e

18 / 78

THE MUSIC LIST

#		Song	Artist	Time	BPM			Album
1		Copper Meridian	Orbital Cartographers	5:05	—		★	Copper Meridian
2		Ein außerorden...	Cassette Bloom	6:21	104		★	Live from Pier 9
3		Harbour Lights	Orbital Cartographers	4:24	—		★	Copper Meridian
4		Lantern Road	Marlow & the Tidewater	3:24	118		★	Quiet Arithmetic
5		Long Wave	Fennel Grove	5:16	122		★	Long Wave Sessions, Vol. 2
6		Midnight Set, Si...	Fennel Grove	2:58	110		★	Long Wave Sessions, Vol. 2
7		Pier 9 (Live)	Cassette Bloom	4:11	—		★	Live from Pier 9
		Quiet Arithmetic	Marlow & the Tidewater	3:51	96		★	Quiet Arithmetic

The same component the player renders, with the reference's stylesheet block: nine columns, 18 px rows, the stripe, no rules, an embossed header with the sorted column tinted, monochrome source badges read from each track's locator, icon columns for offline and star, the playing row in bold with a speaker glyph and a marquee, a right-click menu, and the gel scroller that fades in while you scroll.

THE SEARCH POPOVER

3 matches for "la"Clear

Lantern Road
Marlow & the Tidewater — Quiet Arithmetic

3:24
118 bpm

L

Long Wave
Fennel Grove — Long Wave Sessions, Vol. 2

5:16
122 bpm

YT

Copper Meridian
Orbital Cartographers

5:05
—

H

The iTunes 11 results popover: a gradient header with the count and Clear, 40 px rows whose artwork tile is a fifteen-second audition button with a countdown ring, a circled chevron on the hot row, and a pager. Arrow keys walk the rows and page off the end.

CONTEXT MENU, SHEET AND TOAST

Add to Playlist >

New Playlist...


✓ Road Trip

Late Nights


New Playlist...

New Playlist


Enter a name. "Lantern Road" goes in it.



THE EQUALIZER WINDOW




SHARED MODE, AND THE PAGE'S FURNITURE



The strip under the hero when you are in a group; a section's head and toolbar row; and the status line the bottom bar used to carry.


A LIVE BROADCAST




In shared mode the rail is not yours to drag: the duration stamp becomes the LIVE marker, the fill sits at the live edge, and the rail drops its slider role rather than announcing a control that refuses every change.

THE VISUALISERS — SPECTRUM, STAGE AND CONSTELLATION

The player draws three visualisers, and all three follow one rule: a visualiser must carry the data, not hide it. The two below are drawn here by the player's own code — `drawSpectrum` and `layoutStars` in `music-player/src/lib/`, the functions the views call — in the player's own `.player-spectrum` and `.player-constellation` styles. The third, the **jewel case**, is live on the hero at the top of this chapter.



The spectrum, under “How this is being played” in the Now playing section. Each analyser frame is averaged into 64 bars; a bar's hue and lightness rise with its level, so a loud band reads brighter as well as taller. It draws only while a song plays — paused, the loop stops rather than repaint a still picture — and under reduced motion it redraws four times a second instead of every frame. There is no audio here, so the specimen is fed a generated frame; print shows one fixed frame.




The constellation: the library as a star field, one star per album. Albums by one artist share an angular sector, a star's size is the album's length, and its colour is the artist's hue, so the layout is information, never scatter. The app renders it with WebGL and a slow rotation; this is the same placement projected through the same camera (55°, z = 42), as SVG so it also prints. Hover a star for its album.

The **jewel case** is `packages/aqua-ui/src/stage/jewel-case.ts`: the case and disc built from primitives, sleeve and tray-card textures generated from the track's real cover and running order, a drag with momentum, and a pose remembered per device. It stands in for Cover Flow (DEC-006). The stage and the constellation load Three.js lazily and share the chunk, so a listener who opens neither never downloads it. All three keep their meaning without motion: the spectrum slows to a level, the stage stops its idle drift and keeps the CSS cover, and the constellation opens as the same albums in a table, with identical selection and keyboard behaviour (UX-MOTION-001, UX-STATE-001). Both sections also appear whole in the mockups: *Now playing (audio chain)* and *Constellation*.

The window — what the hub and the companion are made of

The desktop skin: a framed window with traffic lights, a unified toolbar carrying the transport and the LCD, a source list, a work area with a table, and a bottom bar. The hub's admin GUI and the Windows companion are both built from this.



#	Name	Time	Artist	Album	Genre
1	Track 1	3:00	Fennel Grove	Long Wave Sessions	Ambient
2	Track 2	4:07	Cassette Bloom	Live from Pier 9	Indie
3	Track 3	5:14	Orbital Cartographers	Copper Meridian	Electronic
4	Ein außerordentlich langer	6:21	Marlow & the Tidewater	Quiet Arithmetic	Folk
5	Track 5	3:28	Fennel Grove	Long Wave Sessions	Ambient
6	Track 6	4:35	Cassette Bloom	Live from Pier 9	Indie
7	Track 7	5:42	Orbital Cartographers	Copper Meridian	Electronic
8	Track 8	6:49	Marlow & the Tidewater	Quiet Arithmetic	Folk
9	Track 9	3:56	Fennel Grove	Long Wave Sessions	Ambient
10	Track 10	4:03	Cassette Bloom	Live from Pier 9	Indie
11	Track 11	5:10	Orbital Cartographers	Copper Meridian	Electronic
12	Track 12	6:17	Marlow & the Tidewater	Quiet Arithmetic	Folk
13	Track 13	3:24	Fennel Grove	Long Wave Sessions	Ambient
14	Track 14	4:31	Cassette Bloom	Live from Pier 9	Indie
15	Track 15	5:38	Orbital Cartographers	Copper Meridian	Electronic
16	Track 16	6:45	Marlow & the Tidewater	Quiet Arithmetic	Folk
17	Track 17	3:52	Fennel Grove	Long Wave Sessions	Ambient
18	Track 18	4:59	Cassette Bloom	Live from Pier 9	Indie
19	Track 19	5:06	Orbital Cartographers	Copper Meridian	Electronic
20	Track 20	6:13	Marlow & the Tidewater	Quiet Arithmetic	Folk
21	Track 21	3:20	Fennel Grove	Long Wave Sessions	Ambient

Every part of that window is a component: `AquaWindow`, `Toolbar`, `TrafficLights`, `Transport`, `LcdDisplay`, `Scrubber`, `VolumeSlider`, `SearchField`, `SegmentedControl`, `AvatarButton`, `SourceList`, `WorkArea`, `Content`, `AquaTable`, `Marquee`, `NowPlayingGlyph`, `BottomBar`, `IconButton`.

Controls

Shared by both skins and all three products, verbatim.

Buttons: neutral / default / graphite / destructive / busy / disabled / small / mini / ellipsis / link

Cancel

Save

Graphite

⚠ Delete Playlist

⚙ Importing

Disabled

Small

Mini

Export...

Pressed

⬇ Download · 84 MB

Icon buttons: framed / plain / capsule / pressed / menu / disabled / large

⚙

☆

📁

🔗

☰

⬇

🚗

Checkbox / radio / text field / validation / pop-up

☒ Show explicit content

☒ Some folders

☐ Disabled

☒ Ask each time

☐ Windows only

Display name

Reference tuning

Disabled

Jalon

528

●

—


Shown to group members

● Reference must be between 400 and 480 Hz

Default format


Original

⬆⬇⬆




Overlays

Sheets attach to their window; alerts stand alone; menus open where they are asked for and return focus to what asked. Press the buttons.



States — the group people skip

Every screen owes an answer for empty, loading, offline, partial, refused and out-of-date. `UnavailableCapabilityState` exists so that “this cannot work here” is a designed state carrying its reason, rather than a blank pane.



Couldn't play this song

The file could not be decoded.

Skip

▼ Details

MEDIA_ERR_SRC_NOT_SUPPORTED — audio/x-ape is not decodable in this browser.



Upgrade required

This hub speaks protocol 3; this player supports up to 1.
Nothing was changed.

Reconnect Folder

This browser needs permission again to read "Music".

Reconnect Folder

Remove



Download unavailable

YouTube does not permit audio downloads.

▼ Why unavailable?

The provider does not permit this — YouTube API Services Terms prohibit downloading audio.

Inline state + status dots + panel / form rows / list view



EQ unavailable for this source

Embedded YouTube audio is not exposed to Web Audio, so the equalizer is bypassed.

Audio

RETUNE

Reference tuning

440 Hz (standard)



Mode



Preserve tempo



Linked speed

Cents −31.77

Ratio 0.98182

Latency 43 ms

DEVICES

Studio PC

Windows companion · last seen 2 min ago



Kitchen

Player · online



Hub reachable



EQ unavailable



Refused




No

Status dots carry their text; colour is never the only signal.


Results and grid

The window skin's results popover — the same idea as the page's, at the toolbar's height — and the artwork grid.



Icons

Three families: sixteen-pixel colour source icons for the sidebar, single-colour glyphs for everything else, and the avatar set.



By product

Which element each product imports today, read from its source. The player is the page skin plus the shared controls; the hub and the companion are the window skin plus the same controls.

ELEMENT	PLAYER (PWA)	HUB ADMIN	COMPANION
PageBar	•	—	—
BarSearch	•	—	—
BarClock	•	—	—
ModeSwitch	•	—	—
ProfileButton	•	—	—
SectionStrip	•	—	—
Hero	•	—	—
HeroArt	•	—	—
JewelStage	•	—	—
TrackScrubber	•	—	—
KeyTransport	•	—	—
KeyButton	•	—	—
LevelSlider	•	—	—
MusicList	•	—	—
ButtonLink	•	—	—
IconButton	•	—	—
InlineValidation	•	—	—
SegmentedControl	•	—	—
Sheet	•	—	—
Slider	•	—	—
AquaTable	•	•	•
Button	•	•	•
Checkbox	•	•	•
EmptyState	•	•	•
Glyph	•	•	•
KeyValueList	•	•	•
Panel	•	•	•
PanelSection	•	•	•
PopUpMenu	•	•	•
ProgressBar	•	•	•

ELEMENT	PLAYER (PWA)	HUB ADMIN	COMPANION
SourceBadge	•	•	•
StatusDot	•	•	•
TextField	•	•	•
ToastProvider	•	•	•
useToast	•	•	•
LoadingState	•	•	—
AquaWindow	—	•	•
Toolbar	—	•	•
SourceList	—	•	•
WorkArea	—	•	•
Content	—	•	•
BottomBar	—	•	•
SearchField	—	•	•
ErrorState	—	•	—

The player also draws the search popover, the New Playlist sheet, the toast and the equalizer window with the page skin's classes (shown above) rather than through a component; their stylesheet block is the reference's own.

Interaction and content rules

Every rule has a stable ID. Cite it in a change that touches the behaviour, and change the rule, the owning code and its test together. **Adopted** rules are the standard; **observed** ones describe what the code does today and have not been ratified. The source is `design/ux-rules.json`.

PRINCIPLES THAT OUTRANK THE VISUALS

UX-PRIN-001 **A control that cannot act is not drawn**

● ADOPTED

No button that looks live and does nothing, no toggle whose state is decoration. If an action is impossible in this context the control is omitted or replaced by an explained state.

The equalizer window ships without traffic lights: three circles that close nothing would be decoration.

OWNED BY `music-player/src/views/Equalizer.tsx`

CHECKED BY reviewer Judgement call, checked in review (`docs/AQUA_CONFORMANCE.md`).
`docs/DEVIATIONS.md`

UX-PRIN-002 **An unavailable capability says so where the choice is made**

● ADOPTED

Not in a tooltip, not in a log, not by disappearing. The control stays visible and, when chosen, reports the reason instead of acting.

The Shared segment of the mode switch stays visible with no hub paired and reports why when pressed.

OWNED BY `packages/aqua-ui/src/components/PageBar.tsx` `packages/aqua-ui/src/components/States.tsx`

CHECKED BY `packages/aqua-ui/tests/dom/page-chrome.test.tsx` — “reports the reason instead of switching when a mode is unavailable”
`music-player/tests/e2e/np/livevol.spec.ts` — “the radio transport: Previous and Next read as unavailable, Play does not, and they say why”

UX-PRIN-003 **Say what the code does, not what the feature is called**

● ADOPTED

Labels describe the implemented behaviour. When a label and the DSP (or the network, or the provider) disagree, the label changes.

Solfeggio presets are described as filters with no claimed physical effect; retuning states that the fallback changes tempo.

OWNED BY `music-player/src/views/Equalizer.tsx` `music-player/src/views/Settings.tsx`

CHECKED BY `music-player/tests/e2e/np/connect.spec.ts` — “the companion, the container and backup”
`music-player/tests/e2e/helper.spec.ts` — “a link the helper will not fetch from is refused, with the reason”

UX-PRIN-004 **A disabled control is still legible about why**

● ADOPTED

Greyed, not gone. The reason is part of the accessible name, not only a tooltip.

“500 Hz band, not used by 528 Hz (MI)”.

OWNED BY `music-player/src/views/Equalizer.tsx`

CHECKED BY `music-player/tests/e2e/np/connect.spec.ts` — “the companion, the container and backup”

UX-KEY-001 One tab stop per group; arrows move inside it

● ADOPTED

Source lists, the section strip, the mode switch, tab strips, tables and menus use a roving tabIndex. Home/End jump, Enter activates, type-ahead selects. Focus travels with the selection.

OWNED BY packages/aqua-ui/src/components/SourceList.tsx packages/aqua-ui/src/components/SectionStrip.tsx
packages/aqua-ui/src/components/AquaTable.tsx packages/aqua-ui/src/components/MusicList.tsx
docker-container/src/web/App.tsx

CHECKED BY docker-container/tests/e2e/a11y.spec.ts — “@a11y the tab strip is navigable with the keyboard alone”
packages/aqua-ui/tests/dom/source-list.test.tsx — “has one tab stop, moves with arrows, Home/End, selects with Enter and supports type-ahead”
packages/aqua-ui/tests/dom/table.test.tsx — “uses a roving tabIndex, arrow navigation, Space selection and Enter activation”
packages/aqua-ui/tests/dom/page-chrome.test.tsx — “has one tab stop, moves with arrows and Home/End, chooses with Enter, and answers type-ahead”

UX-FOCUS-001 Focus is always visible

● ADOPTED

Every focusable element shows --aqua-focus-shadow or a 2px --np-accent outline at 2px offset, including when the ring is drawn on an ancestor via :focus-within.

OWNED BY packages/aqua-ui/src/styles/aqua.css packages/aqua-ui/src/styles/now-playing.css

CHECKED BY music-player/tests/e2e/a11y.spec.ts — “@a11y focus is visible wherever it lands”

UX-KEY-002 Every action is reachable with the keyboard alone

● ADOPTED

Every section and every transport control can be reached and operated without a pointer. Space toggles playback without scrolling the page.

OWNED BY music-player/src/App.tsx docker-container/src/web/App.tsx

CHECKED BY music-player/tests/e2e/a11y.spec.ts — “@a11y the transport is reachable and named from the keyboard alone”
music-player/tests/e2e/player.spec.ts — “space toggles playback and does not scroll the page”
docker-container/tests/e2e/a11y.spec.ts — “@a11y the tab strip is navigable with the keyboard alone”

UX-TOUCH-001 Nothing interactive is under 44px on a coarse pointer

● ADOPTED

Under (pointer: coarse) controls grow; where the visual cannot grow, a transparent ::after takes the taps. Desktop keeps its 18px rows. Hit targets are never shrunk to match a visual; --aqua-hit is 32px on desktop, 44px on touch.

OWNED BY packages/aqua-ui/src/styles/aqua.css packages/aqua-ui/src/styles/now-playing.css

CHECKED BY music-player/tests/e2e/responsive.spec.ts — “nothing overflows, no text under 12px, no target under 44px”
music-player/tests/e2e/responsive.spec.ts — “the desktop keeps the design it was drawn with”
packages/aqua-ui/tests/e2e/styleguide.spec.ts — “every screen of every product fits at every size”

UX-TOUCH-002 **No text under 12px on touch; field text is 16px**

● ADOPTED

The touch layer steps the scale up (15/14/13/12/11px). A field's text is 16px because iOS zooms the page when a smaller field takes focus.

OWNED BY packages/aqua-ui/src/styles/aqua.css packages/aqua-ui/src/styles/now-playing.css

CHECKED BY music-player/tests/e2e/responsive.spec.ts — “settings, where every panel of explanatory text lives”

STATES, FEEDBACK AND MOTION

UX-STATE-001 **Every data view answers empty, loading and error**

● ADOPTED

A view that fetches renders LoadingState while waiting, ErrorState with a retry when it fails, and an EmptyState that says what to do next. Blank panes are defects.

OWNED BY docker-container/src/web/views/common.tsx docker-container/src/web/ViewBoundary.tsx
packages/aqua-ui/src/components/States.tsx

CHECKED BY music-player/tests/e2e/np/stats.spec.ts — “before any play: nothing recorded, and no generated source on offer”
music-player/tests/e2e/player.spec.ts — “opens with no music, says so, and raises no errors”

UX-MOTION-001 **Motion confirms; reduced motion is a contract**

● ADOPTED

Nothing animates that a person did not just cause. Under prefers-reduced-motion the live dot stops, marquees hold their ellipsis, sheets fade without travel, and the 3D stage stops drifting. New animations read --aqua-anim-state or --aqua-sheet-travel.

OWNED BY packages/aqua-ui/src/styles/aqua.css packages/aqua-ui/src/styles/now-playing.css
packages/aqua-ui/src/components/Marquee.tsx

CHECKED BY music-player/tests/e2e/a11y.spec.ts — “@a11y respects reduced motion: nothing loops that a person did not start”
packages/aqua-ui/tests/unit/aqua-conformance.test.ts — “§17.5”

UX-FEED-001 **Progress says what is happening in words**

● ADOPTED

Progress bars carry a name and a value; an indeterminate bar is aria-busy and has text. Live regions are polite and carry one sentence.

OWNED BY packages/aqua-ui/src/components/ProgressBar.tsx packages/aqua-ui/src/components/Toast.tsx

CHECKED BY packages/aqua-ui/tests/dom/controls.test.tsx — “progress has a name and value; indeterminate is busy with text”

UX-A11Y-001 **Roles are true and colour is never the only signal**

● ADOPTED

A rail that cannot be dragged is role=img, not a slider that refuses changes. Icon buttons have names. The playing row has a glyph as well as a tint; status dots carry text.

OWNED BY packages/aqua-ui/src/components/Scrubber.tsx packages/aqua-ui/src/components/IconButton.tsx
packages/aqua-ui/src/components/Badge.tsx

CHECKED BY packages/aqua-ui/tests/dom/controls.test.tsx — “live scrubber is not a slider and shows the LIVE marker”
packages/aqua-ui/tests/dom/controls.test.tsx — “icon buttons require names; menu affordance sets aria-haspopup”

UX-LINK-001 **A download is a link**

● ADOPTED

Downloads and destinations in another tab use ButtonLink (an `<a>` wearing the button face), never a `<button>` that assigns location.

OWNED BY packages/aqua-ui/src/components/Button.tsx

CHECKED BY music-player/tests/e2e/np/stats.spec.ts — “after real plays: the page counts them, and export and import round-trip them”

TRUST, SAFETY AND DESTRUCTIVE ACTIONS

UX-SAFE-001 **Destructive actions are worded plainly and confirmed**

● ADOPTED

The button names the consequence (“Forget this hub”, “Remove folder”), sits apart from the default action, and the hub and companion ask before doing it.

OWNED BY packages/aqua-ui/src/components/Sheet.tsx docker-container/src/web/views/Devices.tsx
windows-companion/src/renderer/views/Folders.tsx

CHECKED BY packages/aqua-ui/tests/dom/controls.test.tsx
docs/AQUA_CONFORMANCE.md
reviewer Each new destructive action is reviewed for wording and confirmation.

UX-SAFE-002 **The bootstrap password must be replaced before anything else**

● ADOPTED

admin/admin signs in once, straight into Change password. Every setup-gated screen refuses until then, and the hub stays on loopback outside a container.

OWNED BY docker-container/src/web/App.tsx docker-container/src/auth/service.ts

CHECKED BY docker-container/tests/integration/setup-and-pairing.test.ts — “refuses every setup-gated route until the password is changed”
docker-container/tests/e2e/a11y.spec.ts — “@a11y the sign-in screen has no detectable violations”

UX-SAFE-003 **Pairing is confirmed by comparing a fingerprint**

● ADOPTED

A device receives a scoped credential only after the administrator confirms the fingerprint shown on both screens. Codes are never listed again after they are issued.

OWNED BY docker-container/src/web/views/Devices.tsx docker-container/src/pairing/service.ts

CHECKED BY docker-container/tests/integration/setup-and-pairing.test.ts — “issues a scoped credential only after the fingerprint is confirmed”

UX-SAFE-004 **Privacy claims are stated where they can be checked**

● ADOPTED

Copy that says nothing is uploaded, copied or moved must be true of the code path beside it, and the player loads nothing from outside its own origin.

OWNED BY music-player/src/views/Settings.tsx music-player/src/views/Metrics.tsx

CHECKED BY music-player/tests/e2e/helper.spec.ts — “fetching a link puts a real track in the library, and it plays from this device”
music-player/tests/e2e/player.spec.ts — “loads nothing from outside its own origin, including three.js”

SHARED LISTENING AND THE DISCORD BOT

UX-SHARED-001 **The shared queue rejects stale commands and says so**

● ADOPTED

Every queue command carries the revision it was based on. A stale command is refused with the current revision, never applied over someone else's change.

OWNED BY docker-container/src/group/service.ts packages/domain/src/queue.ts

CHECKED BY docker-container/tests/integration/groups-and-queue.test.ts

UX-DISCORD-001 **Slash and prefix commands behave identically**

● ADOPTED

Both transports run through one CommandService and render the same templates; the only difference is how the reply is delivered.

OWNED BY docker-container/src/group/command-service.ts docker-container/src/discord/gateway.ts

CHECKED BY docker-container/tests/integration/discord-parity.test.ts — “produces identical outcomes for every command”

UX-DISCORD-002 **Refusals are private and say what was needed**

● ADOPTED

permissionDenied, noResults, unavailableSource, emptyQueue, wrongChannel and error replies are ephemeral and name the reason or the channel to use.

OWNED BY packages/domain/src/templates.ts docker-container/src/group/command-service.ts

CHECKED BY docker-container/tests/integration/discord-parity.test.ts — “applies the same permission decision on both transports”

UX-DISCORD-003 **The bot never goes silent without a reason**

● ADOPTED

A track the bot cannot play is skipped with the reason recorded; a failed decode advances as an error; the admin panel shows the voice state and last error.

OWNED BY docker-container/src/discord/voice.ts docker-container/src/discord/worker.ts

CHECKED BY docker-container/tests/unit/discord-voice.test.ts — “skips a track it cannot play instead of going silent”

docker-container/tests/integration/discord-worker.test.ts — “shows the worker's live status in the hub”

WORDS

VOICE-001 **Empty states say what to do next**

● OBSERVED

Title names the situation in a few plain words (“Nothing queued”); text gives the next action or the reason. No apologies, no exclamation marks.

“Nothing queued — Play something from your library and it will appear here.”

OWNED BY music-player/src/views/Queue.tsx windows-companion/src/renderer/views/Transfers.tsx

CHECKED BY music-player/src/views/Queue.tsx

VOICE-002 **Errors explain the problem and the way out**

● ADOPTED

Name what failed in the person's terms and what fixes it (“Add a bot token first (Admin → Discord → Token)”). Never show a stack trace or an internal identifier; a 500 carries a correlation id instead.

OWNED BY docker-container/src/app.ts docker-container/src/discord/service-interface.ts

CHECKED BY docker-container/src/discord/service-interface.ts

VOICE-003 **One product name, set in one place**

● ADOPTED

“Now Playing” and the product names come from BRANDING in TypeScript. Native resources that cannot import it (Android strings.xml, the SVG icons' aria-labels, the Electron builder config) repeat it and must be changed together.

OWNED BY packages/contracts/src/branding.ts android/app/src/main/res/values/strings.xml
 music-player/public/icon.svg windows-companion/resources/icon.svg

CHECKED BY packages/contracts/tests/branding.test.ts
 packages/contracts/src/branding.ts

PLAYER SHELL — PRINCIPLES

NP-PRIN-001 **One component, one reference**

● ADOPTED

Every component reconstructs one named Apple release (iPod classic, iTunes 10, OS X 10.6, iOS 5...) and is sampled from it, not averaged. Eras mix across components, never inside one. The reference is written beside the component's tokens.

The contextual menu is OS X 10.6 (opaque, 5px radius, 20px rows, 13px text); the action sheet that replaces it on touch is iOS 5/6.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/menuverify.spec.ts — “era metrics, keyboard nav intact, escape closes, menu action still fires”
 music-player/tests/e2e/np/menuverify.spec.ts — “dark menu opaque”

NP-PRIN-002 **Unavailable is shown and explained, never hidden**

● ADOPTED

A control that cannot act in this context stays visible and focusable, is marked aria-disabled, looks disabled, and says why when pressed or hovered. It is not removed and it does not silently do nothing.

On a station, previous and next are greyed, titled 'Not available for radio', and pressing them says 'Pick another station from the list'.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/livevol.spec.ts — “the radio transport: Previous and Next read as unavailable, Play does not, and they say why”
 music-player/tests/e2e/np/radio.spec.ts — “the tab opens on stations, not on a menu, and the panel is the song list's own rules”
 music-player/tests/e2e/np/func.spec.ts — “avatar gradient not black; the transport at rest is a slider with every key reachable”

Numbers shown to the listener come from what actually happened. A track's seconds come from the transport's own clock (a seek is not a listen); stream time is measured from playing to pause/end; anything under five seconds is not a session; a film or song counts as finished only when it played to its end. No invented history, no sample figures — with one labelled exception: Statistics shows a generated demo year while this player has recorded nothing, and says so in the Data menu, the source line and Your data (NPD-023).

Statistics opens on this player's own history once anything has played; before that, on a demo year that says it is one.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/prefs.spec.ts — “opening: Settings is a page with its own address, and the toolbar is the navigation”
music-player/tests/e2e/np/prefs.spec.ts — “it is a page at both widths, and a section has its own address”
music-player/tests/e2e/np/discover.spec.ts — “a track's seconds are measured, not assumed”

Colour, gradient and metric values are CSS custom properties on :root. Components read variables. The dark list is written twice (Auto and forced Dark) and the two copies must be identical.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY reviewer Carried from airwave-np; its test did not survive the port as a separate assertion. Checked in review against the shell.

PLAYER SHELL — PERIOD FIDELITY

Menus, sheets and popovers of this period had no vibrancy. Their backgrounds are opaque in both themes; only the iOS HUD is translucent.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/menuverify.spec.ts — “dark menu opaque”

Selected rows and highlighted menu items use the era's two-stop vertical gradient with white text: iTunes 10 blue in lists (--lib-sel-*), Aqua blue in menus (--ctx-hi-*), iPod blue on the iPod screen (--ipod-sel-*).

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY reviewer Carried from airwave-np; its test did not survive the port as a separate assertion. Checked in review against the shell.

PLAYER SHELL — LIVE AND BROADCAST

NP-LIVE-001 **A live feed says LIVE where the time would be**

● ADOPTED

On Live TV the video controller replaces the elapsed/duration readout with a red LIVE badge, from the moment the tab opens (not only after a channel plays). The badge is centred on the progress rail horizontally in its box and vertically on the rail's centre line at every width.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/livevol.spec.ts — “the Live TV tab is live before a channel is chosen, and a channel does not follow you on to TV”
music-player/tests/e2e/np/devices.spec.ts — “: the LIVE readout sits right, idle and playing”
music-player/tests/e2e/np/livevol.spec.ts — “LIVE on the video bar: the tab is live on arrival and a channel keeps it so”

NP-LIVE-002 **The progress of a broadcast does not move and cannot be seeked**

● ADOPTED

During a live feed the scrubber is an image (role=img, no range ARIA), the channel loops so LIVE stays true, and pressing it explains instead of seeking.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/livevol.spec.ts — “LIVE on the video bar: the tab is live on arrival and a channel keeps it so”
music-player/tests/e2e/np/func.spec.ts — “24px optical offset preserved; sort headers are buttons and sorting works; page has h1”
music-player/tests/e2e/np/func.spec.ts — “avatar gradient not black; the transport at rest is a slider with every key reachable”

PLAYER SHELL — TRANSPORT AND SOUND

NP-TRANS-001 **One source sounds at a time**

● ADOPTED

Starting a station stops the video; starting a channel or film stops the station. A film does not follow the listener onto the Live TV or TV tab.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/livevol.spec.ts — “one thing at a time: a channel stops the station, and tuning back stops the channel”
music-player/tests/e2e/np/livevol.spec.ts — “the Live TV tab is live before a channel is chosen, and a channel does not follow you on to TV”

NP-TRANS-002 **The volume control owns every sound**

● ADOPTED

The volume slider drives the station and the video as well as music; Home is silence and mutes, End is full, the level survives a change of station and a reload.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/livevol.spec.ts — “volume reaches the stream: the slider, Home and End, and a new station keeps the level”
music-player/tests/e2e/np/livevol.spec.ts — “the level is remembered across a reload”

NP-TRANS-003 **Video starts at the highest quality**

● ADOPTED

A channel, episode or film opens on its highest available rendition; the quality menu lets the viewer step down.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/media.spec.ts — “Live TV: the guide replaces the song list, the video player takes the top, and a channel plays”

NP-TRANS-004 **The equalizer never silences what it cannot process**

● ADOPTED

Audio is routed through the equalizer only when the browser allows processing it (same-origin, blob:, data:, or the companion). Cross-origin streams play unequalized, and the pane says so.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/prefs.spec.ts — “opening: Settings is a page with its own address, and the toolbar is the navigation”

PLAYER SHELL — MENUS AND COMMANDS

NP-MENU-001 **Right-click opens the item's commands; keys work inside**

● ADOPTED

Right-clicking a song, station, channel, series or film opens an OS X contextual menu at the pointer with the commands for that kind of item. Arrow keys move, Return chooses, Escape closes and returns focus. Scrolling the page after opening does not close it instantly.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/menuverify.spec.ts — “era metrics, keyboard nav intact, escape closes, menu action still fires”
music-player/tests/e2e/np/lists.spec.ts — “the song menu is untouched”
music-player/tests/e2e/np/lists.spec.ts — “Radio: a station is played, kept or filed; a new playlist holds it and can be emptied”

NP-MENU-002 **On touch, a long press raises an action sheet**

● ADOPTED

Touch devices get the same commands as an iOS action sheet from a long press, with Cancel last.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/menuverify.spec.ts — “long press raises action sheet, listing all commands + playlists + cancel, and its action fires”

NP-MENU-003 **Confirmation is a HUD, not a dialog**

● ADOPTED

A command that completes (added to a playlist, removed) confirms with a brief HUD naming what happened. Dialogs are only for commands that need more input.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/menuverify.spec.ts — “era metrics, keyboard nav intact, escape closes, menu action still fires”
music-player/tests/e2e/np/menuverify.spec.ts — “long press raises action sheet, listing all commands + playlists + cancel, and its action fires”

NP-MENU-004 **One menu for several songs**

● ADOPTED

Right-clicking inside a selection of several songs opens the contextual menu for all of them: its heading says how many, and each command names the count it will act on — Download N Songs (or Remove N Downloads when all are saved), Add N Songs to Group Queue, Add to Playlist ▸ (ticked only when the playlist holds every one), New Playlist from N Songs..., Deselect All. The selection survives the repaint a command causes.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/marquee.spec.ts — “dragging draws a selection box, and the menu for several acts on all of them”

PLAYER SHELL — LISTS AND PLAYLISTS

NP-LIST-001 **Every tab has playlists, behind the library button**

● ADOPTED

Music, Radio, Live TV, TV and Movies each keep their own playlists. They are reached from the library (menu) button on the left of the scope bar, and filled from the item's contextual menu. They persist across reloads.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/lists.spec.ts — “Radio: a station is played, kept or filed; a new playlist holds it and can be emptied”
music-player/tests/e2e/np/lists.spec.ts — “the playlist is still there after a reload”

NP-LIST-002 **Sorting is a button**

● ADOPTED

Sortable column headers contain buttons and expose aria-sort; the sorted column tints blue (iTunes 10). A set order (a playlist) shows no arrow until a column sort overrides it.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/func.spec.ts — “24px optical offset preserved; sort headers are buttons and sorting works; page has h1”
music-player/tests/e2e/np/ipod.spec.ts — “no column may show a sort arrow while the rows are in set order”

NP-LIST-003 **Drag a box to pick several songs**

● ADOPTED

On a pointer, pressing on a song row's empty space and dragging draws a rubber band; every row it touches is selected. Cmd/Ctrl-click adds or removes one song, Shift-click takes the range, Cmd/Ctrl-A takes the list, Escape clears. Picking is never playing: the click that ends a drag, and a modified click, start nothing. A plain click goes back to one song and plays it.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/marquee.spec.ts — “dragging draws a selection box, and the menu for several acts on all of them”

PLAYER SHELL — HEADER AND NAVIGATION

NP-CHROME-001 **The header search belongs to Music**

● ADOPTED

The status bar's search pill searches songs and takes pasted song links, so it is shown only on Music. Other tabs search with the list's own field.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/hdr.spec.ts — “the header field is up on Music and gone on the other tabs, which keep their own field”

NP-CHROME-002 **The profile button opens Settings**

● ADOPTED

The avatar at the right of the status bar opens Settings as its own page (#settings), not a pop-up.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/prefs.spec.ts — “opening: Settings is a page with its own address, and the toolbar is the navigation”

NP-CHROME-003 **A mini player while Settings is open; leaving video stops it**

● ADOPTED

When Music or Radio is the tab and Settings covers the player, the header's search pill becomes a mini player: title and artist, time and duration, play/pause and skip, driving the real transport. Leaving a video tab — for Settings or another tab — pauses a film or episode, and disconnects Live TV (the stream is closed, not just muted).

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/mini.spec.ts — “with Settings open, the header shows a mini player that drives the real transport”
music-player/tests/e2e/np/mini.spec.ts — “video tabs: Settings from Live TV shows no mini player and disconnects; Music pauses a channel”

PLAYER SHELL — PREFERENCES

NP-PREF-001 **Two idioms: iPhone OS on phones, a toolbar on desktops**

● ADOPTED

Below 720px Settings is an iPhone OS drill-down: an index of 44px rows, a back button that names where it returns to. From 720px it is a preferences window with a toolbar of five panes. The browser Back button walks the same history.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/prefs.spec.ts — “media playlists live behind the library button”
music-player/tests/e2e/np/prefs.spec.ts — “opening: Settings is a page with its own address, and the toolbar is the navigation”

NP-PREF-002 **A preference applies when it is changed**

● ADOPTED

No Save and no Apply. Theme, motion, artwork, defaults, group mode and every algorithm setting apply immediately and persist (player:prefs). Revert, in the footer, restores everything to how it was when Settings opened (NPD-016).

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/prefs.spec.ts — “opening: Settings is a page with its own address, and the toolbar is the navigation”
music-player/tests/e2e/np/prefs.spec.ts — “player preferences, the equalizer and group mode; the equalizer survives a reload”
music-player/tests/e2e/np/discover.spec.ts — “Revert puts back the weight, the algorithm, and removes the copy”

NP-PREF-003 **The algorithm is editable and cannot be made invalid**

● ADOPTED

Every recommendation setting has a control. Rules the engine enforces (weights summing to 100, ranges) are checked as the user edits and offered a fix, never silently clamped.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/prefs.spec.ts — “opening: Settings is a page with its own address, and the toolbar is the navigation”

NP-PREF-004 **Built-in algorithms never change**

● ADOPTED

Airwave default, Late night and Crate digger are read-only. The first change to one makes a named copy, selects it and says so; built-ins cannot be renamed or deleted. Delete asks twice.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/discover.spec.ts — “built-ins, copies, rename, duplicate, delete, export, import, and a reload”

NP-PREF-005 **Algorithms move as files, and imports say what they read**

● ADOPTED

Export writes one algorithm (or all of yours) as an airwave-algorithm JSON file; Import takes those or a bare engine config, reads only keys the engine knows with values of the right type, and reports how many settings it read and how many it ignored.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/discover.spec.ts — “the shelf records what it shows, and plays from it count”
music-player/tests/e2e/np/discover.spec.ts — “built-ins, copies, rename, duplicate, delete, export, import, and a reload”

NP-PREF-006

Settings controls are Mac OS X controls, drawn over native elements

● ADOPTED

Push buttons, pop-ups and checkboxes in Settings wear Mac OS X drawings: Snow Leopard (10.6) push buttons — a matte, brushed-metal pill with a graphite hairline, blue when pressed — and 10.4 Aqua pop-ups (white body, blue arrow segment) and gel checkboxes that AquaArt draws from sampled colour profiles and publishes as custom properties. The elements stay native button, select and checkbox, so keyboard, forms and screen readers are unchanged. 22px on desktop, 30px on touch; the drawings and their black labels are the same in both themes (NPD-021).

OWNED BY `music-player/index.html` `music-player/scripts/make-shell.py`**CHECKED BY** `music-player/tests/e2e/np/aqua.spec.ts` — “buttons, pop-ups and checkboxes wear the Aqua drawings and still work”
`music-player/tests/e2e/np/aqua.spec.ts` — “the 30px drawings on a phone”

NP-PREF-007

Connections show what answered and what goes where

● ADOPTED

Sources ▶ Connections tests the Windows companion app (GET /helper/v1/health; an empty address scans 127.0.0.1:17342–17345) and the Docker container (GET /healthz, /readyz, /api/v1/hub; port 4546), using the AudioWave repo's own endpoints; and Stream from a PC pairs with the companion's AWSP sidecar by its ticket and six-digit code (docs/AWSP.md §2), then shows the PC's name, the connection type (relay-carried in a browser) and how many of its tracks joined the library, with the same lights. Each test shows what came back — version, downloaders, allowed sites, readiness checks, fingerprint, encryption — with a green, amber or red light; every request goes in the connection log with its status and time; and the What's passed table lists each setting, where it goes, and 'Ready' only once that destination has answered.

OWNED BY `music-player/index.html` `music-player/scripts/make-shell.py`**CHECKED BY** `music-player/tests/e2e/np/connect.spec.ts` — “the companion, the container and backup”
`music-player/tests/e2e/awsp.spec.ts` — “pairs, plays relay-carried, is bit-identical, seeks by range, and resumes across a relay restart”

NP-PREF-008

Backups say what they need before they run

● ADOPTED

Sources ▶ Backup chooses what to copy (Music, TV, Movies; playlists, EQ presets and settings) and where (the Docker container, the Windows companion app, or both), and how often. Media moves between the companion app and the container, so it needs both to have answered a test and its folder to be set; settings need only their destination. Back Up Now stays disabled and says which of those is missing; once it runs, the request is written to the connection log and What's passed lists a backup row per destination.

OWNED BY `music-player/index.html` `music-player/scripts/make-shell.py`**CHECKED BY** `music-player/tests/e2e/np/connect.spec.ts` — “the companion, the container and backup”

NP-PREF-009

Profiles live on the container, and names are unique there

● ADOPTED

Once the player is paired with the Docker container (the hub's own /pairing/claim, /status and /complete, confirmed by fingerprint), Settings gains a Profile tab: a username, a picture cropped to 256 × 256, and playlists shared as CSV (title, artist, album, seconds), all saved to the container and never kept in the browser. A username someone else has — compared without case — is caught as you type and refused on save. Search lists people on the container above songs; a profile opens in a sheet with their picture, name and shared playlists, and a song you also have can be played from it. Your picture takes the jewel case's place on the Music page. Until the container has the profile routes, the tab says so.

OWNED BY music-player/index.html music-player/scripts/make-shell.py**CHECKED BY** music-player/tests/e2e/np/profile.spec.ts — “pair, edit the profile on the container, find someone, open their profile”

NP-PREF-010

One default volume for every source

● ADOPTED

Settings ▸ Equalizer ▸ Default volume sets the level Airwave opens at — where you left it, or a fixed default — and Set Volume Now moves the bar's volume to it. Music, radio, Live TV, TV and films all start at and follow that one volume.

OWNED BY music-player/index.html music-player/scripts/make-shell.py**CHECKED BY** music-player/tests/e2e/np/volume.spec.ts — “the default volume: Set Volume Now, then each start mode across a reload”

NP-PREF-011

A backup says how big it is and whether it fits

● ADOPTED

Settings ▸ Sources ▸ Backup shows the expected size, part by part, and each destination's free space as a bar (in use · this backup · free after it). Figures the player can't measure itself come from the companion app and the container; until they answer, the row names which figure is waiting and who measures it. Back Up Now is unavailable when the backup doesn't fit. Algorithms can be backed up like the rest. Sizes are decimal (1 GB = 10⁹ bytes).

OWNED BY music-player/index.html music-player/scripts/make-shell.py**CHECKED BY** music-player/tests/e2e/np/connect.spec.ts — “the companion, the container and backup”

NP-PREF-012 Groups and invites live on the Profile tab

● ADOPTED

Settings ▶ Profile lists your groups on the container with their member count and your role, makes a new one (you own it), and — for an owner or admin whose player was paired with the “Manage groups” permission — makes an invite link that works once and expires after the time chosen. Without that permission no invite link is offered, because the container would refuse it, and the message names the missing permission rather than blaming the role. Invites you have received wait there until you join or decline; ones you have sent show who they were for and when they expire. A code the container can't withdraw is never shown as withdrawn.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/groups.spec.ts — “the Profile tab: groups, a new group, an invite link, Withdraw, and Leave”
music-player/tests/e2e/np/groups.spec.ts — “paired without “Manage groups”, no group offers an invite link — the hub would refuse it”
tests/journey/cross-app.spec.ts — “the whole pass: hub set up, player paired, group joined, invite declined, name taken, group owned, someone found”

NP-PREF-013 An invite link opens an invite page

● ADOPTED

Opening an invite link shows a page naming the group, who sent it, the container, the role and when it expires, with Join Group and Decline (Not Now keeps it waiting). What the link says is labelled as the link's until the container confirms it. An unpaired player, or one paired with another container, is asked to pair first and offered Connections. The code is taken out of the address bar as soon as it has been read.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/groups.spec.ts — “the invite page: from a link, Not Now, Join, a used code, a bad code, Decline”
music-player/tests/e2e/np/groups.spec.ts — “not paired: the invite page asks you to pair first”

PLAYER SHELL — STATISTICS AND CHARTS

NP-DATA-001 One hue for amounts, named hues for genres, and every chart as numbers

● ADOPTED

Amounts use one hue (--viz-1) with a single-hue ramp for the skyline (--viz-sky-0 → --viz-1 → --viz-peak). Genres use seven token hues (--viz-g1...g7, --viz-g0 for the rest), lifted in dark, and a genre's colour never appears without its name beside it. Every chart has its value written beside it or a table under it, and the 3D views are backed by the same numbers in 2D.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/stats.spec.ts — “before any play: nothing recorded, and no generated source on offer”

NP-DATA-002 **Every figure is set against the period before**

● ADOPTED

For 7, 30, 90 days and the year, each tile compares with the period of the same length just before it, with ▲/▼, the figure, and colour for good or bad news (more skips is up and bad). All time has no period before and shows no comparison. Heard-to-the-end and skips count only plays the transport timed (NPD-018).

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/discover.spec.ts — “statistics against the period before, and the recommendation funnel”

NP-DATA-003 **Recommendations are counted from the shelf's own record**

● ADOPTED

What Discover shows is logged once per song per day; a play started there is a recommendation taken. The funnel reads recommended → started → heard to the end → replayed → added or favourited from those logs, never from estimates.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/discover.spec.ts — “the shelf records what it shows, and plays from it count”
music-player/tests/e2e/np/discover.spec.ts — “statistics against the period before, and the recommendation funnel”

NP-DATA-004 **The statistics page works without its 3D views**

● ADOPTED

Statistics loads three.js from the page's import map the first time it opens. If that fails or takes more than eight seconds, each 3D well says it couldn't load and the page carries on; every 3D view has the same numbers in 2D or in a table. A theme change repaints the wells, scenes and labels from the tokens.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/stats.spec.ts — “before any play: nothing recorded, and no generated source on offer”
music-player/tests/e2e/np/stats.spec.ts — “the wells say so, the tables stay”

PLAYER SHELL — LAYOUT ACROSS DEVICES

NP-RESP-001 **The video controller fits the player, not the window**

● ADOPTED

Controller-bar content responds to the player's width (container queries): elapsed only under 560px, download and touch volume hidden, More hidden under 358px; the scrubber keeps at least 60px. Checked at 18 device sizes.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/devices.spec.ts — “: the LIVE readout sits right, idle and playing”
music-player/tests/e2e/np/livevol.spec.ts — “px LIVE is centred in its box, clear of its neighbours, and the scrubber keeps room”

NP-RESP-002 **Picture and controls fit under the status bar**

ADOPTED

On short screens (landscape phones, short laptops) the video player is capped so it and its controls fit below the status bar without scrolling.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/devices.spec.ts — “: the LIVE readout sits right, idle and playing”

PLAYER SHELL — ACCESSIBILITY

NP-A11Y-001 **Every control is reachable and named**

ADOPTED

Icon-only controls carry accessible names; groups of choices are radiogroups moved with arrow keys; scrolling regions are focusable; headings give the page an outline (one h1).

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/func.spec.ts — “24px optical offset preserved; sort headers are buttons and sorting works; page has h1”
music-player/tests/e2e/np/prefs.spec.ts — “opening: Settings is a page with its own address, and the toolbar is the navigation”

NP-A11Y-002 **Motion stops when asked**

ADOPTED

With the OS reduced-motion setting, or Preferences > Reduce animation, pulses, barber poles, spinners and transitions stop.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/prefs.spec.ts — “opening: Settings is a page with its own address, and the toolbar is the navigation”

NP-A11Y-003 **Text meets 4.5:1; exceptions are recorded**

ADOPTED

Text/background pairs listed in design/foundations.json meet WCAG 2.2 AA (4.5:1 text, 3:1 marks) in both themes. Period colours that fall short are recorded as decisions, never added silently.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY reviewer Carried from airwave-np; its test did not survive the port as a separate assertion. Checked in review against the shell.

PLAYER SHELL — VOICE AND COPY

NP-VOICE-001 **Commands are Title Case; an ellipsis means a dialog follows**

ADOPTED

Menu commands use Title Case verbs ('Go to Album', 'Add to Playlist'). An ellipsis marks exactly the commands that open a dialog for more input ('New Playlist...', 'Change Artist...').

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/menu2.spec.ts — “six commands in three groups, and an ellipsis marks exactly the dialog commands”

NP-VOICE-002 The verb matches the thing

● ADOPTED

A song or film is Played, a channel is Watched, a series is Opened. Commands that make no sense for a kind of item are absent from its menu, not disabled.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY music-player/tests/e2e/np/lists.spec.ts — “Live TV: a channel is watched, not played, and its playlist still reads as a guide”
music-player/tests/e2e/np/lists.spec.ts — “Radio: a station is played, kept or filed; a new playlist holds it and can be emptied”
music-player/tests/e2e/np/lists.spec.ts — “the song menu is untouched”

NP-VOICE-003 Explanations are one plain sentence with a way forward

● ADOPTED

When something cannot happen, say what to do instead in one sentence, without apology or error codes: 'Pick another station from the list', 'Couldn't reach search — open it on a platform instead:'.

OWNED BY music-player/index.html music-player/scripts/make-shell.py

CHECKED BY reviewer Carried from airwave-np; its test did not survive the port as a separate assertion. Checked in review against the shell.

Accessibility

Not bolted on afterwards. These are parts of the design.

- **One tab stop per group, arrows to move.** The section strip, the mode switch, the music list and the context menu all use a roving `tabIndex`, and the focus ring travels with the selection.
- **Focus is always visible.** An end-to-end test tabs the whole page and fails on any element that shows no indicator.
- **Roles must be true.** A rail that cannot be dragged is `role="img"` with no value pair, not a slider that refuses every change. A button that opens a section does not claim `aria-haspopup="menu"`.
- **Names say what will happen**, including the refusal.
- **Colour is never the only signal.** The playing row has a glyph as well as a tint; status dots carry text.

Every screen

Every surface found in the products' own navigation, with the states it has to answer and the rules that govern it. `pnpm styleguide:check` rebuilds this list from the `ViewId` declarations, the sheet files and the Discord command table, and fails when something appears that is not recorded in `design/coverage.json`.

Seen running: opened in the running product for this revision (see Coverage). **Mockup only:** rendered at every size in the mockups from the real components with fixture data. **Not run here:** the product could not be started where this guide was built. **Source only:** checked against the code, not looked at.

MUSIC PLAYER

Page skin. The PWA, the single-file build, the Android app and the local helper all show this.

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Status bar, mode switch, hero and section strip (React specimen, not served — DEC-019) every section <code>music-player/src/App.tsx</code> <code>packages/aqua-ui/src/components/PageBar.tsx</code>	- nothing playing - playing - paused - live stream (read-only scrubber) - unknown duration - shared unavailable (reason shown) - narrow (strip scrolls) - transport: volume beneath when it cannot flank the keys (DEC-016) - transport: keys wrapped, previous/play/next alone on the first line (DEC-016)	UX-PRIN-002 UX-KEY-001 UX-KEY-002 UX-TOUCH-001	● seen running
Music Library (React specimen, not served — DEC-019) section strip → Music Library <code>music-player/src/views/Library.tsx</code> <code>packages/aqua-ui/src/components/MusicList.tsx</code>	- empty (how to add music) - scanning - loaded - sorted - selected row - playing row - unplayable format	UX-KEY-001 UX-STATE-001 UX-A11Y-001 VOICE-001	● seen running
Now playing (React specimen, not served — DEC-019) section strip → Now playing <code>music-player/src/views/NowPlaying.tsx</code> <code>packages/domain/src/visualisers/spectrum.ts</code>	- nothing playing - playing (spectrum moving) - paused (spectrum stopped) - reduced motion (spectrum at 4 per second) - equalizer not applied (reason shown) - shared (group queue)	UX-STATE-001 UX-MOTION-001	○ mockup only
Queue (React specimen, not served — DEC-019) section strip → Queue <code>music-player/src/views/Queue.tsx</code>	- nothing queued - queued - shuffled - shared (hub revision)	UX-STATE-001 UX-SHARED-001 VOICE-001	● seen running
Playlists (React specimen, not served — DEC-019) section strip → Playlists <code>music-player/src/views/Playlists.tsx</code>	- no playlists - list - playlist open - empty playlist	UX-STATE-001 VOICE-001	○ source only

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Search (React specimen, not served — DEC-019) status-bar search → Enter music-player/src/views/Search.tsx music-player/src/components/SearchPopover.tsx	- prompt (device only / with hub) - searching hub - no local matches - results - hub unreachable	UX-STATE-001 UX-PRIN-002	☐ source only
Listening history (React specimen, not served — DEC-019) section strip → Listening history music-player/src/views/Metrics.tsx	- nothing yet - history	UX-STATE-001 UX-SAFE-004	☒ seen running
Constellation (React specimen, not served — DEC-019) section strip → Constellation music-player/src/views/Constellation.tsx packages/domain/src/visualisers/constellation-layout.ts	- nothing to map - field - table (equivalent view) - reduced motion (table) - WebGL unavailable	UX-MOTION-001 UX-STATE-001	☐ mockup only
Settings and equalizer (React specimen, not served — DEC-019) profile button in the status bar music-player/src/views/Settings.tsx music-player/src/views/Equalizer.tsx	- no folders - folders - hub paired - hub not paired - equalizer on/off - solfeggio preset (dimmed bands) - crossfade - car/lock-screen report	UX-PRIN-001 UX-PRIN-003 UX-PRIN-004 UX-LINK-001 UX-TOUCH-002 UX-SAFE-004	☒ seen running
Add to playlist (React specimen, not served — DEC-019) + beside the transport, or row menu music-player/src/components/AddToPlaylistSheet.tsx	- open - no playlists	UX-KEY-001	☐ source only
New playlist (React specimen, not served — DEC-019) Playlists → New, or row menu music-player/src/components/NewPlaylistSheet.tsx packages/aqua-ui/src/components/music-list-behaviours.tsx	- empty name (validation) - valid	VOICE-002	☐ source only
Download from the hub (React specimen, not served — DEC-019) row menu → Download music-player/src/components/DownloadSheet.tsx	- choose format - basis required - in progress - failed with reason	UX-FEED-001 UX-PRIN-002	☐ source only

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Fetch with a local tool (React specimen, not served — DEC-019) Library → Fetch (when a helper or the Android tools are present) music-player/src/components/FetchSheet.tsx music-player/src/lib/fetch-helper.ts	- no tool (control hidden) - url entry - running - finished (files) - failed (tool's own reason)	UX-PRIN-001 UX-FEED-001 VOICE-002	☐ source only
Share (React specimen, not served — DEC-019) share button beside the transport, or a playlist music-player/src/components/ShareSheet.tsx	- no hub (explains why) - link created - copied	UX-PRIN-002	☐ source only
Search popover (React specimen, not served — DEC-019) typing in the status-bar search music-player/src/components/SearchPopover.tsx	- counting - results - none - dismissed (arrow brings back)	UX-FEED-001 UX-KEY-001	☒ seen running
Notice bar and toasts (React specimen, not served — DEC-019) any warning the store raises music-player/src/components/NoticeBar.tsx packages/aqua-ui/src/components/Toast.tsx	- info - warning - dismissed	UX-FEED-001 VOICE-002	☒ seen running
Row context menu (React specimen, not served — DEC-019) right-click or the row's menu key packages/aqua-ui/src/components/music-list-behaviours.tsx	- open - disabled items with reason	UX-KEY-001 UX-PRIN-004	☐ source only
Library the list under the player; Music view music-player/index.html music-player/scripts/make-shell.py	- empty (nothing indexed) - rows from this device - link rows from search - sorted - narrowed by scope chip - filtered by the bar	NP-LIST-001 UX-KEY-001 UX-STATE-001	☐ source only
Now Playing the jewel case and transport at the top of the page music-player/index.html music-player/scripts/make-shell.py	- nothing playing - a track from this device playing (the bar follows the element) - paused - a link row chosen (does not pretend to play) - a station (LIVE) - a channel (video bar, LIVE)	NP-TRANS-001 UX-KEY-002	☐ source only
Search popover the header search field music-player/index.html music-player/scripts/make-shell.py	- empty - results from companion / iTunes - pasted link resolved - people on the hub	NP-PRIN-002	☐ source only

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Row menu right-click or long-press a row music-player/index.html music-player/scripts/make-shell.py	- one row - several rows (marquee)	NP-MENU-001	○ source only
New playlist sheet row menu ▸ Add to Playlist ▸ New Playlist... music-player/index.html music-player/scripts/make-shell.py	- empty name refused - created	NP-MENU-002	○ source only
Fetch sheet transport ▸ Download, on a link row music-player/index.html music-player/scripts/make-shell.py	- no basis chosen (refused, said why) - helper found / not found - fetching - refused by the helper (its reason) - fetchd and playing	UX-SAFE-001 UX-FEED-001	○ source only
Mini player the header while Settings is open music-player/index.html music-player/scripts/make-shell.py	- hidden - shown for music and radio	NP-CHROME-001	○ source only
Radio toolbar ▸ Radio music-player/index.html music-player/scripts/make-shell.py	- directory unreachable (offline shelf) - a station playing - station list	NP-LIVE-001	○ source only
Live TV toolbar ▸ Live TV music-player/index.html music-player/scripts/make-shell.py	- no playlist loaded (empty guide) - channels from a loaded M3U - a channel playing (LIVE)	NP-LIVE-002	○ source only
TV toolbar ▸ TV music-player/index.html music-player/scripts/make-shell.py	no catalogue (nothing invented)	NP-PRIN-001	○ source only
Movies toolbar ▸ Movies music-player/index.html music-player/scripts/make-shell.py	no catalogue (nothing invented)	NP-PRIN-001	○ source only
Settings ▸ Statistics profile button ▸ Statistics, or #settings/stats music-player/index.html music-player/scripts/make-shell.py	- nothing recorded yet - this player's history - imported file 3D views unavailable (tables still carry the numbers)	NP-DATA-001	○ source only
Settings ▸ Recommendations #settings/rec music-player/index.html music-player/scripts/make-shell.py	- defaults - edited - saved algorithm - reverted	NP-PREF-001	○ source only

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Settings ▶ Sources #settings/src music-player/index.html music-player/scripts/make-shell.py	- music on this device (folders/files) - companion found / missing downloaders - hub tested / paired - backup measured (nothing sent) - backup will not fit (reason)	NP-PREF-002 UX-FEED-001	○ source only
Stream from a PC #settings/src ▶ Connections ▶ Stream from a PC; the indicator beside the transport while a PC track plays music-player/index.html music-player/scripts/make-shell.py	- not paired - not a ticket / not six digits (refused before sending, said why) - pairing - wrong code / code expired or used (the PC's answer, in words) - paired and connected: PC name, relay-carried, track count - reconnecting (the PC or its relay is away) - refused (revoked on the PC: pair again) - a PC track playing: indicator reads relay-carried - single-file copy: unavailable, and says so	NP-PREF-007 NP-PRIN-002 UX-FEED-001	○ source only
Settings ▶ Player #settings/player music-player/index.html music-player/scripts/make-shell.py	- appearance - listening - defaults	NP-PREF-003	○ source only
Settings ▶ Equalizer #settings/eq music-player/index.html music-player/scripts/make-shell.py	- preset - custom - default volume	NP-PREF-004	○ source only
Settings ▶ Profile #settings/profile (shown when paired) music-player/index.html music-player/scripts/make-shell.py	- name available / taken - picture - shared playlists - groups - invites received / sent - declined	NP-PREF-005 UX-SAFE-001	○ source only
Profile viewer search ▶ a person, or a group member music-player/index.html music-player/scripts/make-shell.py	- their name, picture and shared playlists - a playlist opened	NP-PREF-005	○ source only
Invite page a #invite/<code> link music-player/index.html music-player/scripts/make-shell.py	- previewed (group, sender, role, expiry) - unknown or used code - joined - declined	NP-PREF-005	○ source only

HUB ADMIN AND PUBLIC PAGES

Window skin, served by the container on port 4546.

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Sign in any admin URL without a session docker-container/src/web/App.tsx	- first run (admin/admin hint) - wrong password - rate limited	UX-SAFE-002 VOICE-002	● seen running
Change the bootstrap password first sign-in docker-container/src/web/App.tsx	- weak password refused - saved	UX-SAFE-002	○ source only
View error boundary any admin view that throws docker-container/src/web/ViewBoundary.tsx	error with retry	UX-STATE-001	○ source only
Overview Overview tab docker-container/src/web/views/Overview.tsx docker-container/src/web/views/common.tsx	- loading - loaded (tiles: hub, connections, groups, providers, storage, jobs) - error - alerts (count on the Overview tab)	UX-STATE-001 UX-KEY-001	○ mockup only
Devices and pairing Devices tab → Devices docker-container/src/web/views/Devices.tsx	- no devices - pairing code shown - claim waiting for fingerprint - revoke (confirm)	UX-SAFE-001 UX-SAFE-003 UX-STATE-001	○ source only
Groups Groups tab docker-container/src/web/views/Groups.tsx	- no groups - group with queue - archived - new group - invite made (code shown once) - invite withdrawn (confirm)	UX-SHARED-001 UX-STATE-001	○ source only
Providers Music tab → Providers docker-container/src/web/views/Providers.tsx	- available - sign in needed - not configured - off - test result	UX-PRIN-002 UX-A11Y-001	○ mockup only
Library Music tab → Library docker-container/src/web/views/Library.tsx	- no roots - scanning - tracks	UX-STATE-001	○ source only
Downloads Music tab → Downloads docker-container/src/web/views/Downloads.tsx	- queued - running - paused - failed with reason - completed - formats unavailable without FFmpeg	UX-FEED-001 UX-PRIN-002	○ mockup only
Profiles Devices tab → Profiles docker-container/src/web/views/Profiles.tsx	- none - listed - renaming - name taken - remove picture (confirm)	UX-SAFE-001 UX-FEED-001	○ source only

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Shared links Sharing tab → Shared links docker- container/src/web/views/Shares.tsx	• none • active • revoked (confirm)	UX-SAFE-001	○ source only
Recommendations Music tab → Recommendations docker- container/src/web/views/Recommendations.tsx	• defaults • edited	UX-PRIN-003	○ source only
Discord Sharing tab → Discord docker- container/src/web/views/Discord.tsx docker-container/src/discord/service-interface.ts	• no token • configured but disabled • worker not running • connected • voice playing • last error • template preview	UX-PRIN-002 UX-DISCORD-003 VOICE-002	○ source only
Network System tab → Network docker- container/src/web/views/Network.tsx	• localhost • lan • remote (restart required)	UX-SAFE-002	○ source only
Backup System tab → Backup docker- container/src/web/views/Backup.tsx	• no backups • list • restore (confirm) • restore failed with reason • space measured • space unknown • next backup will not fit	UX-SAFE-001 UX-STATE-001	○ source only
Diagnostics System tab → Diagnostics docker- container/src/web/views/Diagnostics.tsx	• loaded	UX-STATE-001	○ source only
Public share page /s/<token> docker- container/src/api/routes/shares.ts DEC-008	• track or playlist • stream allowed • link unavailable	UX-SAFE-004	○ source only

WINDOWS COMPANION

Window skin in an Electron window.

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Folders Library tab → Folders (Saved Music · Saved TV · Saved Movies) windows- companion/src/renderer/views/Folders.tsx	• no folders • watching • drive not connected • remove (confirm)	UX-SAFE-001 VOICE-001	○ not run here

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Music Library tab → Music windows-companion/src/renderer/views/Library.tsx	- nothing indexed - no matches - tracks	UX-STATE-001 VOICE-001	○ not run here
Connection Remote tab → Hub connection windows-companion/src/renderer/views/Hub.tsx	- not paired - pairing (fingerprint) - connected - plain-http warning - forget (confirm)	UX-SAFE-001 UX-SAFE-003	○ not run here
Transfers Remote tab → Transfers windows-companion/src/renderer/views/Transfers.tsx	- nothing transferring (paired / not paired) - uploading - cancelled - failed	UX-FEED-001 VOICE-001	○ not run here
Backup Settings tab → Backup windows-companion/src/renderer/views/Backup.tsx	- no folder chosen (Back Up Now disabled, reason shown) - measuring - fits / does not fit (space bar: used this backup · free) - running with progress - archives listed - restore (confirm) - delete (confirm)	UX-SAFE-001 VOICE-002	○ not run here
About Settings tab → About windows-companion/src/renderer/views/About.tsx	loaded	VOICE-003	○ not run here
Live TV Live TV tab windows-companion/src/renderer/views/LiveTv.tsx	- not available yet (amber, no sample channels) - TV folders listed	UX-PRIN-001	○ not run here
Settings Settings tab → Settings windows-companion/src/renderer/views/Settings.tsx	- downloaders found / missing (amber, with what to install) - helper running / not running with reason - port invalid - token shown / hidden	UX-PRIN-001 UX-FEED-001	○ not run here
Notice bar any main-process notice windows-companion/src/renderer/views/NoticeBar.tsx	- info - warning	VOICE-002	○ not run here

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Stream to your devices Remote tab → Stream to your devices windows-companion/src/renderer/views/Streaming.tsx windows-companion/src/main/awsp.ts	• off (default) • starting • running: ticket, QR and pairing code • sidecar missing or crashed (reason, restarting) • devices paired, each direct / relay-carried / not connected • revoke (confirm) • port invalid	UX-SAFE-001 UX-FEED-001 UX-PRIN-002	○ not run here

DISCORD BOT

Messages rendered from templates the operator can edit.

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Bot replies /play, /queue, /skip ... or the prefix form docker-container/src/discord/gateway.ts packages/domain/src/templates.ts DEC-005	• queued • now playing • skipped / vote counted • refused (ephemeral) • no results • cannot be played here • joined / left voice • not in a voice channel • missing Connect/Speak	UX-DISCORD-001 UX-DISCORD-002 UX-DISCORD-003	○ not run here

ANDROID SHELL

A WebView around the player, plus system UI.

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
WebView shell launcher icon android/app/src/main/java/com/nowplaying/player/MainActivity.kt android/app/src/main/res/values/strings.xml DEC-012	• player loaded from assets • renderer crashed (reloads) • back = history, else background • hub over http refused	UX-SAFE-004	○ not run here
Notification, picker and save dialog a fetch starts; a file input opens; an export is saved android/app/src/main/java/com/nowplaying/player/FetchService.kt android/app/src/main/java/com/nowplaying/player/BlobDownloads.kt DEC-010	• fetching (foreground notification) • permission prompt (API 33+) • saved • could not save	VOICE-002	○ not run here

LOCAL HELPER

A console program that serves the player and runs download tools.

SURFACE	STATES IT MUST ANSWER	RULES	SEEN
Local helper console now-playing-helper local-helper/src/cli.ts local-helper/src/options.ts	- tools found / missing with install hint - token shown - stopping	VOICE-002	○ not run here

Journeys

The ten things people come to do, from where they start to where they can fail. Each step list is what the code does today; each failure is one the product answers in words.

First run of the hub

A fresh data volume; the container is up on 127.0.0.1:4546.

1. Open the admin page
2. Sign in with admin / admin
3. Choose a real password
4. Every section unlocks

WHEN IT GOES WRONG

- Weak password refused with the reason
- Login rate-limited after repeated failures

UX-SAFE-002

docker-container/tests/integration/setup-and-pairing.test.ts
docker-container/tests/e2e/first-run.setup.ts

Pair a player or the companion

Setup complete; the device can reach the hub.

1. Admin creates a pairing code (Devices)
2. Device enters the code
3. Both screens show the same fingerprint
4. Admin confirms
5. Device receives a scoped credential

WHEN IT GOES WRONG

- Code expired
- Fingerprint differs: do not confirm
- Wrong codes lock out that address for a while

UX-SAFE-003

docker-container/tests/integration/setup-and-pairing.test.ts

Pair with a PC and play its music, relay-carried

The companion app runs its AWSP sidecar on a PC; the player is the served build (a service worker is the bridge).

1. On the PC, Settings ▶ Remote shows a ticket and a six-digit code
2. In the player, Sources ▶ Connections ▶ Stream from a PC: paste the ticket, type the code, Pair
3. The card shows the PC's name, relay-carried, and its track count; the tracks join the library
4. Play one; the bar follows the element and the indicator beside the transport reads relay-carried
5. The relay drops mid-track; the player reconnects and carries on from the last byte it held

WHEN IT GOES WRONG

- A wrong or expired code is refused in words, and nothing is stored
- A revoked player is told to pair again, and stops reconnecting
- The single-file copy has no service worker, and says streaming needs the served player

NP-PREF-007 NP-PRIN-002

music-player/tests/e2e/awsp.spec.ts

windows-companion/awsp-server/tests/awsp.rs

Add music on this device and play it

The player is open (installed or not).

1. Library shows how to add music
2. Choose a folder or files
3. Tracks appear; unplayable formats say so
4. Play; the hero and the list mark the playing row

WHEN IT GOES WRONG

- Browser without folder access falls back to file choice
- A file that disappeared says it cannot be found

UX-STATE-001 UX-A11Y-001

music-player/tests/e2e/local-file.spec.ts

music-player/tests/e2e/player.spec.ts

Listen together

Player paired with a hub; a group exists.

1. Switch the mode to Shared
2. Join or create a group
3. Anyone queues; everyone hears it at the same point
4. Skips and pauses apply to the group

WHEN IT GOES WRONG

- No hub: the switch explains why
- Stale command: refused with the current revision
- Member without the DJ role: vote-skip instead of skip

UX-PRIN-002 UX-SHARED-001

docker-container/tests/integration/groups-and-queue.test.ts

Play music into a Discord voice channel

Bot token installed, bot enabled, default group chosen, worker container running.

1. Join a voice channel
2. /play <search or link>
3. The bot joins your channel and replies Queued
4. Audio follows the group timeline; pause, skip and seek from any device apply

WHEN IT GOES WRONG

- Not in a voice channel: the reply says so
- Missing Connect/Speak: the reply names them
- Source that cannot stream in Discord: skipped with the reason
- Worker not running: the admin panel says so

UX-DISCORD-001 UX-DISCORD-002 UX-DISCORD-003

docker-container/tests/integration/discord-worker.test.ts

docker-container/tests/unit/discord-voice.test.ts

docker-container/tests/integration/discord-parity.test.ts

Download a track the hub may give you

Paired player; the provider allows it.

1. Row menu → Download
2. Choose format and the basis (e.g. content I own)
3. Progress in words
4. The file saves as a link download

WHEN IT GOES WRONG

- Format unavailable without FFmpeg
- Provider refuses the basis
- Cancelled: the partial file is removed

UX-FEED-001 UX-LINK-001

`docker-container/tests/security/ssrf-and-downloads.test.ts`

`docker-container/tests/integration/downloads-queue.test.ts`

Share a track or playlist

Paired player.

1. Share
2. Choose whether streaming is allowed
3. Copy the link
4. The recipient opens the public page

WHEN IT GOES WRONG

- No hub: the sheet explains why
- Link revoked or used up: the page says it is unavailable

UX-PRIN-002

`docker-container/tests/integration/shares-and-sync.test.ts`

`docker-container/tests/security/share-limits.test.ts`

Send files from Windows to the hub

Companion paired; a folder indexed.

1. Add a folder
2. Select tracks in Music
3. Send to the hub
4. Transfers shows progress; cancel stops it

WHEN IT GOES WRONG

- Drive not connected
- Hub unreachable: upload fails with the reason

UX-FEED-001

`windows-companion/tests/integration/companion-and-hub.test.ts`

Back up and restore

Setup complete.

1. Backup → Create
2. Restore → confirm
3. The hub reports success or the reason it failed

WHEN IT GOES WRONG

- Invalid backup refused
- Swap failed: previous database put back

UX-SAFE-001

`docker-container/tests/integration/backup-and-search-cursor.test.ts`

Fetch with yt-dlp or spotDL

The local helper is running, or the Android app has unpacked its tools.

1. Library → Fetch
2. Paste a link and pick a format
3. Progress
4. Files are added to the library

WHEN IT GOES WRONG

- Tool missing: the control is not shown
- Tool error: its own message, without paths

UX-PRIN-001 VOICE-002

`music-player/tests/e2e/helper.spec.ts`

`local-helper/tests/integration/helper-server.test.ts`

The Discord bot

The bot is the one surface Aqua does not draw: Discord does. What the suite controls is the words, the embed colour, whether a reply is private, and when the bot moves in and out of voice. Replies come from templates an operator can edit in the hub (Admin → Discord); these are the defaults, rendered with sample values by the same function the bot uses.

Commands: `/play` `/nowplaying` `/queue` `/skip` `/pause` `/resume` `/stop` `/shuffle` `/clear` `/join` `/leave` `/settings`. Every one also works as a prefix command (`!play`) once the Message Content intent is granted, and the two forms are identical by construction ([UX-DISCORD-001](#)). Embed colours are the system's own: selection blue, success, warning and danger.

Illustration — Discord renders its own interface. This shows content and colour, not Discord's layout.

success A command with nothing more specific to say	Done.
queued <code>/play</code> found something playable	Queued #3 Signal Fade — Cassette Bloom Requested by alex · 0:04 · Public domain
nowPlaying <code>/nowplaying</code>	Now Playing Signal Fade — Cassette Bloom Live from Pier 9 Requested by alex in Kitchen
skipped <code>/skip</code> by a DJ or the requester	Skipped Signal Fade (skipped).
permissionDenied The caller lacks the DJ or admin role only the caller sees this	You don't have permission to do that (the DJ role is required).
noResults <code>/play</code> found nothing only the caller sees this	No results for “No results”.
unavailableSource The match cannot stream in Discord only the caller sees this	Signal Fade cannot be played here: YouTube only plays in its own player.
emptyQueue <code>/queue</code> or <code>/nowplaying</code> with nothing queued only the caller sees this	The queue is empty. Use <code>/play</code> to add something.
joined <code>/join</code> , or <code>/play</code> when the bot was not in voice	Joined #music.
left <code>/leave</code> , or the idle timeout	Left the voice channel.

error Anything unexpected; the reason is the error message only the caller sees this	Something went wrong: Queue is at revision 12
wrongChannel A command outside the designated channel only the caller sees this	Music commands work in #music.
paused /pause	Paused.
resumed /resume	Resumed.
stopped /stop	Stopped and cleared the queue.
shuffled /shuffle	Shuffled 12 tracks.
cleared /clear	Cleared 12 tracks from the queue.

VOICE-CHANNEL REPLIES

Added to the reply when the bot cannot move into voice. They are sentences in the gateway, not templates.

- “Join a voice channel first (or use join <channel>), so I know where to play.”
- “I need View Channel, Connect and Speak in <channel> to play there.”
- “There is no voice channel called “<name>” that I can see.”
- “Could not connect to the voice channel. Check that the bot has Connect and Speak there, and that outbound UDP is not blocked.”

Known gap (DEC-005). The default `noResults` template quotes `{{reason}}`, but the command service passes the search text as `title`, so a failed search currently reads “No results for “No results”.”

Platforms

WEB AND PWA — PLAYER AND HUB ADMIN

- **Breakpoints follow content, not a device list.** The page skin changes at 480, 560, 620, 720 and 900px; the window skin at 479, 599 and 759px, where the source list gives way and the current source is named in the toolbar. Check at the mockup sizes: 320, 390, 768, 1280 and 1680px.
- **The pointer decides density, not the width.** (`pointer: coarse`) switches the touch layer on at any width; a narrow desktop window keeps desktop density ([UX-TOUCH-001](#)).
- **Installable and offline.** The player ships a manifest, icons and a service worker, opens with the network off once it has loaded online, and loads nothing from another origin. The single-file build, `now-playing.html`, runs straight from disk.
- **Themes.** The page skin follows the system colour scheme; a page can pin itself light with `data-np-theme="light"`. The window skin is light only (DEC-003).
- **Keyboard.** Space toggles playback, the section strip and source lists move with the arrow keys, and Escape closes a popover without losing what was typed.

ANDROID

- The app is the player inside a WebView, loaded from its own assets, so every web rule applies unchanged. The player is built with `NP_BASE_PATH=/assets/app/`.
- Back goes back in the page's history; with nowhere to go it moves the app to the background, so music keeps playing.
- System UI carries its own copy (`strings.xml`): the "Fetching music" notification while a download runs, the document picker for file inputs, and the save dialog for exports ("Saved ..." / "Could not save ..."). Notification permission is asked for the first time a fetch starts (DEC-010).
- Hubs are reached over https only (DEC-012).

WINDOWS COMPANION — ELECTRON

- One window with a source list, and a tray icon (`resources/tray.svg`) whose menu has Open and Quit. With the "minimize to tray" preference on, closing the window keeps the companion running.
- It is the only product that reads the filesystem; its copy says so and never implies files are copied or uploaded in the background.
- Pairing shows the hub's fingerprint and warns when the hub address is plain http off the local network.

TERMINAL — LOCAL HELPER

- Takes the first free port in a small range, prints the token to paste into Settings → Platforms, and names each missing tool with the command that installs it.
- Ctrl+C removes only the helper's own working folder, never the folder it was pointed at.

ENGINEERING APPENDIX — DOCKER DELIVERY

Docker is how the hub is delivered, not a design surface. What it means for a design change:

- The image (`docker-container/Dockerfile`) builds the admin GUI with the same `@now-playing/aqua-ui`, so a token or component change reaches the hub only when the image is rebuilt: `docker compose up -d --build` OR `./nowplaying update`.
- The hub listens on port 4546, published to `127.0.0.1` by default, with `/healthz` for the health check. Host names other than IP addresses, `localhost` and `.local/.lan` names must be listed in `NP_ALLOWED_HOSTS` or set as `NP_PUBLIC_ENDPOINT`.
- The Discord worker is the same image under `--profile discord`. Its default replies change when `packages/domain/src/templates.ts` changes and the image is rebuilt, or immediately when an operator edits a template in the hub.
- The player, the Android app and the companion are built separately; each needs its own rebuild to pick up a design change.

Every product, every size — and editable


Each frame below is an iframe with its own viewport, so a 320px column is a real 320px viewport and this system's media queries behave exactly as they do on a phone. The screens inside are built from the components on this page, so they are 1:1 with the products by construction rather than by somebody keeping two drawings in step. Under each one is a measurement taken *inside* that frame: what runs off the side, the smallest text, the smallest thing you could tap.

A frame marked *touch layer emulated* has this system's (pointer: coarse) rules re-applied inside it, read back out of the real stylesheets — an iframe inherits the desktop's pointer, so without that a phone frame would quietly show desktop sizes. At the bottom you can edit any custom property the stylesheets define and watch every frame repaint at once; what you copy out is a block the three products already read.

In print, every screen is shown at the laptop and phone sizes with the fit measured inside each frame. The interactive version — every size, the product switch and the token editor — is <docs/design/styleguide.html>.


Now playing and library

The whole page skin at once. Narrow it and watch the list drop its number and artist columns and put the artist under the title instead.



Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 10px



Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 12px · smallest target 44px

Settings

Where most of the app's explaining happens, so it is the screen where text size and wrapping matter most.

Settings What this app can do here, and what it cannot — with the reason in each case.

Playback

☒ Crossfade songs

☒ Keep songs from the same album gapless

Platforms

Three questions, because the platforms answer them differently. Every "no" says whose rule it is.

This device ☒ Play here: Yes ☒ Keep offline: Yes ☒ Save a file: Yes

Bandcamp ☐ Play here: No ☐ Keep offline: Sometimes ☐ Save a file: Sometimes

YouTube ☐ Play here: Sometimes ☐ Keep offline: No ☐ Save a file: No

Spotify ☐ Play here: Sometimes ☐ Keep offline: No ☐ Save a file: No

Hub

Hub address

https://living-room.local:4546

Pair

Forget

Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 12px

Settings What this app can do here, and what it cannot — with the reason in each case.

Playback

☒ Crossfade songs

☒ Keep songs from the same album gapless

Platforms

Three questions, because the platforms answer them differently. Every "no" says whose rule it is.

This device ☒ Play here: Yes ☒ Keep offline: Yes ☒ Save a file: Yes

Bandcamp ☐ Play here: No ☐ Keep offline: Sometimes ☐ Save a file: Sometimes

YouTube ☐ Play here: Sometimes ☐ Keep offline: No ☐ Save a file: No

Spotify ☐ Play here: Sometimes ☐ Keep offline: No ☐ Save a file: No

Hub

Hub address

https://living-room.local:4546

Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 13px · smallest target 44px

Now playing (audio chain)

What the audio chain is doing to the song, and the spectrum visualiser under it — drawn by the player’s own spectrum code from a generated analyser frame.

Now playing

What the audio chain is doing to this song, measured rather than assumed.

How this is being played

Song

Midnight Set, Side B — Fennel Grove

Position

0:23 of 2:58

Source

A file on this device

Equalizer

Bass Lift — the preset chosen for this album

Limiter

On — prevents clipping when the equalizer adds gain

Headroom

3.0 dB trim applied to keep the boosted signal below full scale

Retuning

Off — playing at the original pitch

Added latency

11.6 ms

Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 11px

Now Playing styleguide · source 2e5edf99053c1f3e


65 / 78

Now playing

What the audio chain is doing to this song, measured rather than assumed.

How this is being played

Song	Midnight Set, Side B — Fennel Grove
Position	0:23 of 2:58
Source	A file on this device
Equalizer	Bass Lift — the preset chosen for this album
Limiter	On — prevents clipping when the equalizer adds gain
Headroom	3.0 dB trim applied to keep the boosted signal below full scale
Retuning	Off — playing at the original pitch
Added latency	11.6 ms




Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 13px · smallest target —


Constellation

The library as a star field, placed by the player’s own layout code. The table beside it is the same information, not a fallback.



Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 11px




Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 13px · smallest target 44px


Overview

The window skin with a source list. Below about 700px the sidebar gives way and the current source is named in the toolbar instead.



Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 10px




Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 12px · smallest target 44px


Providers

A table inside a window. On a phone the table stacks rather than scrolling sideways.



Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 10px




Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 12px · smallest target 44px


Downloads

Progress and a rights basis. Both are text that has to stay readable when the window is half its width.



Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 10px




Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 12px · smallest target 44px


Folders

The same window skin the hub uses, on a desktop where it is never narrow — which is exactly why it is worth checking that it still holds up when it is.



Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 10px




Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 12px · smallest target 44px


Transfers

Progress, and an empty state that has to say something useful rather than apologise.



Laptop 1280 × 800, shown at 53%

● Fits nothing off the side · smallest text 10px



Phone 390 × 844, shown at 56% touch layer emulated

● Fits nothing off the side · smallest text 12px · smallest target 44px

Sources and commands

This page is generated. The sources below are the design authority: change them, then rebuild. The exports — this page and its PDF — are views, so an edit or annotation on either is a request to change a source, not a change in itself.

CONCERN	SOURCE	OWNS
tokens	<code>packages/aqua-ui/src/styles/tokens.json</code>	Documented values: colour, type, space, size, shadow, motion, page skin.
stylesheets	<code>packages/aqua-ui/src/styles/aqua.css</code> <code>packages/aqua-ui/src/styles/aqua-window.css</code> <code>packages/aqua-ui/src/styles/aqua-media.css</code> <code>packages/aqua-ui/src/styles/now-playing.css</code>	The custom properties every product reads (light scheme on <code>:root</code> , dark and touch layers after it). Mirrors <code>tokens.json</code> by hand; see <code>tokenMap</code> .
tokenMap	<code>design/token-map.json</code>	Which custom property carries each token, and recorded exceptions.
overrides	<code>packages/aqua-ui/src/styles/overrides.css</code>	Temporary cross-product trials written by the styleguide's token editor. Empty in the repository.
components	<code>packages/aqua-ui/src</code>	Every shared control, shell, overlay and state. Imported by the player, the hub admin GUI and the Windows companion.
rules	<code>design/ux-rules.json</code>	Interaction and content rules with stable IDs, their owning code and their tests.
coverage	<code>design/coverage.json</code>	Every surface, state and journey, with discovery sources.
decisions	<code>design/decisions.md</code>	Adopted, proposed and unresolved decisions and exceptions (DEC-###).
prose	<code>docs/design/STYLEGUIDE.md</code>	The reasoning behind the visuals, in long form.
conformance	<code>docs/AQUA_CONFORMANCE.md</code>	Spec §17/§18 MUSTs mapped to tests, reviewer checks or deviations.
specification	<code>docs/design/APPLE_AQUA_2009_2010_UI_DESIGN_SPEC.md</code>	The reconstruction target (Snow Leopard / iTunes 9).

CHANGING SOMETHING

1. Find the owner: a token, a component, a rule by ID, or a surface in the ledger.
2. Change it there — and, for a rule, the code that implements it and the test that proves it.
3. Run `pnpm styleguide:check` and the tests the rule names; then `pnpm styleguide:build` and `pnpm styleguide:pdf`.
4. Look at the result in the mockups at every size, and at every page of the PDF.
5. A deliberate exception goes in `design/decisions.md` with its reason. Never widen an exception to make a check pass.

COMMANDS

STYLEGUIDE:BUILD rebuilds `docs/design/styleguide.html` from the sources above (same as `pnpm build:styleguide`).

D

STYLEGUIDE:CHECK sources and evidence exist, rule IDs are unique, every discovered screen is in the ledger, `tokens.json` matches the stylesheets, and the committed HTML was built from the current sources.

K

STYLEGUIDE:PDF	prints the committed HTML to docs/design/styleguide.pdf with Playwright's Chromium (set NP_STYLEGUIDE_BROWSER to use another Chromium).
E2E	measures every mockup at every size.
CONFORMANCE	includes packages/aqua-ui/tests/unit/aqua-conformance.test.ts and design-sources.test.ts.

Changing any of this

- **Tokens first.** A new colour or size goes in `tokens.json`, then into the stylesheet as a custom property. A literal hex in a component is a bug.
 - **Both schemes.** Light on bare `:root`; redefine only what changes inside the dark guard.
 - **Both skins, if it is a control.** Button, Slider and friends are shared by three products.
 - **Say why in the CSS.** Every unobvious value carries a comment explaining what it reconstructs.
 - **The gates.** `AQUA_CONFORMANCE.md` maps every §17/§18 MUST to a test, a named reviewer check, or a recorded deviation, and `pnpm verify` runs the lot. A deviation is legitimate; an undocumented one is not.
 - **Rebuild this page.** `pnpm styleguide:build` regenerates `docs/design/styleguide.html` from the same source the products use, `pnpm styleguide:check` fails if it no longer matches its sources, and `pnpm styleguide:pdf` prints it.
-

The correction log in `DEVIATIONS.md` is worth reading before a large change. It records the mistakes this system has already made — buttons a decade too glossy, a list redesigned instead of expanded, a picker that indexed music it could never play — and every one was found by building the thing and looking at it.

Coverage and decisions

What this guide covers and how each part was checked, for source revision 2e5edf99053c1f3e. The denominator is every surface in `design/coverage.json`, which the check keeps in step with the products' navigation.

PRODUCT	SURFACES	IN MOCKUPS	SEEN RUNNING	NOT RUN BECAUSE
Music player	37	5	7	—
Hub admin and public pages	17	3	1	—
Windows companion	10	2	0	Electron-only; its renderer needs the preload bridge. Covered by DOM tests and the mockups.
Discord bot	1	0	0	Needs a bot token and a Discord server; covered by the voice and parity tests.
Android shell	2	0	0	No Android SDK or JDK 17 on the machine that built this revision.
Local helper	1	0	0	Console output was not captured for this revision; covered by its integration tests.

Automatic checks when this page was built: 72 rules with evidence, 57 surfaces discovered from navigation, 12 Discord commands, 177 tokens compared with the stylesheets (1 recorded exceptions). No open problems.

recorded exception: `font.family` ↔ `--aqua-font: Lucida Grande, Lucida Sans Unicode, Helvetica Neue, Arial, sans-serif` vs "Lucida Grande", "Aqua Fallback", "Lucida Sans Unicode", "Helvetica Neue", Arial, sans-serif (DEC-002)

SEEN IN A RUNNING PRODUCT

WHEN	SCENARIO	VIEWPORTS · THEME	SURFACES
2026-09-16	Player dev server, empty library, no hub: each section, Settings, search with no match, the Shared segment (toast by pointer and keyboard), and one token change (<code>--np-accent</code>) seen in the player and the rebuilt guide, then reverted. Claude browser pane with DOM measurement	1024×768, 375×812 touch · light	7
2026-09-16	Hub admin dev server against a fresh data folder: the first-run sign-in screen. Signing in was not attempted; it needs a person to enter the password. Claude browser pane	1024×768 · light	1

DECISIONS AND EXCEPTIONS

ID	STATUS	DECISION
DEC-001	● ADOPTED	Lucida Grande is not shipped (not redistributable). The window skin names it first and falls back through a tuned chain.
DEC-002	● ADOPTED	<code>--aqua-font</code> inserts the bundled "Aqua Fallback" face after Lucida Grande; <code>tokens.json font.family</code> does not list it. The CSS is authoritative.
DEC-003	● ADOPTED	The window skin (hub admin, Windows companion) has no dark palette, because Snow Leopard had none. The page skin (player) and the styleguide follow the system colour scheme.

ID	STATUS	DECISION
DEC-005	● UNRESOLVED	Discord <code>noResults</code> renders <code>No results for “{{reason}}”</code> , but the command service passes the search text as <code>title</code> and <code>No results</code> as <code>reason</code> , so the bot says “No results for “No results.”” Proposed fix: the template uses <code>{{title}}</code> . Changing a default template changes what existing servers see.
DEC-006	● ADOPTED	Cover Flow is not implemented; the 3D jewel-case stage stands in for it.
DEC-007	● ADOPTED	The player replaces the inset LCD display with the hero, which states the same information at reading size.
DEC-008	● UNRESOLVED	The public share page (<code>docker-container/src/api/routes/shares.ts</code>) is standalone HTML under a strict CSP with its own inline stylesheet. It uses a 12px pill button and weight 600, which the system otherwise forbids. Proposed: restyle it with the page-skin values (4px push button, weights 400/700).
DEC-009	● ADOPTED	The mockups render each product's real components with fixture data; they are not the product view files executed verbatim. Runtime coverage says which surfaces were seen in the running product and which only in a mockup.
DEC-010	● ADOPTED	Android notifications, the document picker and the save dialog are system UI. The guide documents their copy (<code>strings.xml</code>) and when they appear, not their appearance.
DEC-011	● PROPOSED	<code>tokens.json</code> is mirrored into the stylesheets by hand; <code>pnpm styleguide:check</code> compares the two through <code>design/token-map.json</code> . Proposed: generate the custom properties from <code>tokens.json</code> so the map becomes unnecessary.
DEC-012	● UNRESOLVED	The Android shell only reaches hubs over https (mixed content is never allowed and the manifest forbids cleartext), but the player's pairing form still accepts an <code>http://</code> address, so the refusal happens at connection time. Proposed: say so in the pairing form on Android.
DEC-013	● ADOPTED	The Windows companion is Electron-only; its renderer cannot run in a browser without the preload bridge, so its runtime evidence comes from its DOM tests and the mockups.
DEC-014	● ADOPTED	The equalizer window (<code>.eqw</code>) has an intrinsic width: <code>max-width: 600px</code> , which holds its rails about 36 px apart the way the iTunes window does. It had been stretching to whatever container held it — 958 px in the styleguide — and read as a strip rather than a window.
DEC-015	● ADOPTED	The note in every app icon is placed by centring the path's measured box (x 4.4–19.8, y 3–21.7 of its 24-unit grid) on the icon's optical target: the tile centre for the player and maskable icons, the folder mouth (240, 308) for the companion, the 32-square for the tray. The player icon had shipped 27 px left of centre; <code>tests/unit/icon-glyphs.test.ts</code> now pins all four placements.
DEC-016	● ADOPTED	Play sits on the progress rail's centre line at every width, with previous and next on its line either side. <code>KeyTransport</code> measures its row: the volume line stays beside the keys only while it fits on both sides (otherwise it goes beneath, centred), and the keys wrap only when they do not fit on one line, with previous, play and next alone on the first line. The player's eleven keys never leave room for the volume beside them inside the 820 px hero, so the player shows it beneath at every width. Covered by <code>tests/dom/page-chrome.test.tsx</code> .

ID	STATUS	DECISION
DEC-017	● ADOPTED	The hub admin GUI is the six-tab window of <code>design/frontends/airwave-hub.html</code> (Overview, Devices, Music, Groups, Sharing, System); the thirteen sections keep their data flows and ledger entries and stack inside those tabs, and <code>#section-id</code> in the address still opens the right one. Two departures from that mockup stand. The first-run gate is a screen, not a banner over a disabled interface: the server refuses every gated route until the password is changed, so a live-looking interface behind the banner would be a picture of one. And the invite table shows who an invite is for and its state, not its code, because the hub keeps only a code's hash; the code appears once, when made, and the link needs the address players open Now Playing at. The mockup's <code>warning (#d99a1e)</code> yields to the existing <code>--aqua-warning</code> ; its header and gate colours joined <code>tokens.json</code> as <code>header*</code> and <code>warningBg/warningEdge</code> .
DEC-018	● ADOPTED	The Windows companion is the four-tab window of <code>design/frontends/airwave-companion.html</code> (Library, Live TV, Remote, Settings), on the shared <code>ToolTabs</code> strip. Live TV shows no channels: the repository keeps no M3U or EPG data, so the tab says what is missing in the mockup's amber voice rather than listing samples. The mockup's Remote tab pairs <code>*devices</code> to this PC* with a code; that is the AWSP streaming server's pairing (Phase 4) and arrives with it — until then Remote holds the hub connection and transfers. A backup is a dated folder (<code>data.json</code> + copied folders), measured with <code>local-helper/src/measure.ts</code> so the helper route and this window report one number; sizes are decimal units as the player shows them.
DEC-019	● ADOPTED	The player's interface is the Airwave frontend served as the shell (shape (a) of the master prompt): <code>music-player/index.html</code> is generated from <code>design/frontends/airwave-now-playing.html</code> by <code>music-player/scripts/make-shell.py</code> , every edit asserted against the text it replaces, and <code>src/shell/bridge.ts</code> stands behind the file's seams with <code>db.ts</code> , <code>library.ts</code> , <code>PlaybackEngine</code> , <code>HubClient</code> and bundled <code>three.js</code> . Chosen because the edits that make playback real touch one transport block and one boot block, and the file's twenty-one suites come with it. What the shell no longer contains: the sixteen invented rows, the generated Statistics year, the demo history, the invented TV catalogue, the base64 clips, the two invented albums (now "Nothing playing" / "No group session"), and the direct call to <code>api.anthropic.com</code> (a third-party account). The React interface under <code>music-player/src/{App,views,components}</code> is no longer served; its logic layer (<code>src/lib</code> , <code>src/state</code>) is what the bridge uses. Back Up Now in the player measures and says nothing was sent: no route lets one machine start a backup on another.

NOT COVERED, ON PURPOSE

- `docker-deployment` — Docker is delivery, not a visual surface. Its ports, health check and how rebuilt assets reach users are in the engineering appendix of the styleguide.
- `styleguide` — The styleguide documents the products; it is not one of them.
- `aqua-ui-gallery` — Developer specimen page (`pnpm --filter @now-playing/aqua-ui dev`); its specimens are rendered in the styleguide.